

300 E. Mineral Ave., Suite 10 Littleton, CO 80122-2631 303/781-8211 303/781-1167 Fax

August 31, 2006

Fluid Minerals Group Bureau of Land Management Vernal Field Office 170 South 500 East Vernal, Utah 84078

RE: Application for Permit to Drill—Dominion Exploration & Production, Inc.

RBU 21-18F

Surface Location: 2,379' FSL & 834' FWL Lot 3 (NW/4 SW/4), Target Location: 2,450' FNL & 50' FWL, Lot 2 (SW/4 NW/4), Section 18, T10S, R20E, SLB&M, Uintah County, Utah

Dear Fluid Minerals Group:

On behalf of Dominion Exploration & Production, Inc. (Dominion), Buys & Associates, Inc. respectfully submits the enclosed original and three copies of the Application for Permit to Drill (APD) for the above referenced BLM administered directional 20-acre in-field well. The location of the surface and target location as well as all points along the intended well bore path are not within 460 feet of the unit boundary or any uncommitted tracts. Included with the APD is the following supplemental information:

Exhibit "A" - Survey plats, layouts and photos of the proposed well site;

Exhibit "B" - Proposed location maps with access and utility corridors:

Exhibit "C" - Production site layout;

Exhibit "D" - Drilling Plan;

Exhibit "E" - Surface Use Plan:

Exhibit "F" - Typical BOP and Choke Manifold diagram.

Please accept this letter as Dominion's, written request for confidential treatment of all information contained in and pertaining to this application.

Thank you very much for your timely consideration of this application. Please feel free to contact myself or Carla Christian of Dominion at 405-749-5263 if you have any questions or need additional information.

Sincerely,

Don Hamilton

Agent for Dominion

cc: Diana Whitney, Division of Oil, Gas and Mining Carla Christian, Dominion Ken Secrest, Dominion RECEIVED

AUG 3 1 2006

DIV. OF OIL, GAS & MINING

FII F CODY

CONFIDENTIAL

Form 3160-3 (February 2005)		OM	RM APPROVED IB No. 1004-0137 res March 31, 2007		
UNITED STATES  DEPARTMENT OF THE II  BUREAU OF LAND MANA		5. Lease Serial U013769-A	<u> </u>		
APPLICATION FOR PERMIT TO		6. If Indian, All	lotee or Tribe Name		
ia. Type of work: DRILL REENTE	R	7 If Unit or CA River Ben	Agreement, Name and No. d Unit		
lb. Type of Well: Oil Well Gas Well Other	Single Zone Multip	8. Lease Name le Zone RBU 21-1			
2. Name of Operator  Dominion Exploration & Production, In	ic.	9. API Well No	-047-38554		
3a. Address 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134	3b. Phone No. (include area code) 405-749-5263	10. Field and Poo Natural B			
4. Location of Well (Report location clearly and in accordance with any  At our face 2,379' FSL & 834' FWL Lot 3 (NW/		11. Sec., T. R. M.	or Blk. and Survey or Area		
At surface 2,3/9 FSL & 834 FWL Lot 3 (N W/ At proposed prod. zone 2,450' FNL & 50' FWL, Lot 2 (SW/		Section 18	8, T10S, R20E, SLB&M		
14. Distance in miles and direction from nearest town or post office*  10.02 miles southwest of Ouray, Utah		12. County or Pa Uintah	rish 13. State UT		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig, mit line if any.) 834'	16. No. of acres in lease 791.86 acres	17. Spacing Unit dedicated to	this well		
(Also to nearest drig. unit line, if any)  18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.  10'	19. Proposed Depth  8,650' TVD (8,875' MD)	20. BLM/BIA Bond No. on f WY 3322	ile		
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5,080' GR	22. Approximate date work will sta 01/15/2007	rt* 23. Estimated d 14 days	,		
	24. Attachments				
<ol> <li>Well plat certified by a registered surveyor.</li> <li>A Drilling Plan.</li> <li>A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office).</li> </ol>	4. Bond to cover t ftem 20 above).  Lands, the 5. Operator certification in the steep of the ste	he operations unless covered cation	by an existing bond on file (see		
25. Signature Don Hamilton	Name (Printed/Typed)  Don Hamilton		Date 08/31/2006		
Title Agent for Dominiqu					
Approved by (Signature) Title	Name (Printed/Typed) OfficeRADLEY ( ENVIRONMENTAL	G. HILL MANAGER	Date 91-25-0		
Application approval does not warrant or certify that the applicant hold conduct operations thereon.  Conditions of approval, if any, are attached.	ls legal or equitable title to those rig	nts in the subject lease which v	ould entitle the applicant to		

\*(Instructions on page 2)

CONFIDENTIAL

Federal Approval of this Action is Necessary


RECEIVED AUG 3 1 2006

DIV. OF OIL, GAS & MINING

Surf 609514x 44224177 39.946687 -109.718677

BHU 609271X 44225645 39.948061 -109.720892

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



## APPROVAL OF OPERATIONS

#### **Attachment for Permit to Drill**

Name of Operator:

**Dominion Exploration & Production** 

Address:

14000 Quail Springs Parkway, Suite 600

Oklahoma City, OK 73134

Well Location:

RBU 21-18F

SHL: 2379' FSL & 834' FWL Section 18-10S-20E BHL: 2450' FNL & 50' FWL Section 18-10S-20E

Uintah County, UT

1. GEOLOGIC SURFACE FORMATION

Uintah

#### 2. ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS

<u>Formation</u>	<u>Depth</u>
Wasatch Tongue	4,145'
Uteland Limestone	4,515'
Wasatch	4,675'
Chapita Wells	5,585'
Uteland Buttes	6,835'
Mesaverde	7,725

#### 3. ESTIMATED DEPTHS OF ANTICIPATED WATER. OIL, GAS OR MINERALS

<b>Formation</b>	<u>Depth</u>	Type	
Wasatch Tongue	4.145	Oil	
Uteland Limestone	4,515'	Oil	
Wasatch	4,675'	Gas	
Chapita Wells	5,585'	Gas	
Uteland Buttes	6,835'	Gas	
Mesaverde	7,725'	Gas	

#### 4. PROPOSED CASING PROGRAM

All casing used to drill this well will be new casing.

Type	<u>Size</u>	Weight	Grade	Conn.	Top	<u>Bottom</u>	<u>Hole</u>
Surface	13-3/8"	48.0 ppf	H-40	STC	0,	500'	17-1/2"
Intermediate	9-5/8"	36.0 ppf	J-55	STC	0'	3,325'	12-1/4"
Production	5-1/2"	17.0 ppf	MAV-80	LTC	0,	8,650'	7-7/8"

#### 5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

Surface hole: No BOPE will be utilized.

Intermediate hole: To be drilled using a diverter stack with rotating head to divert flow from rig floor.

<u>Production hole</u>: Prior to drilling out the intermediate casing shoe, 3,000 psi or greater BOP equipment will be installed. The pipe rams will be operated at least once per day from surface to total depth. The blind rams will be tested once per day from surface to total depth if operations permit.

#### APPROVAL OF OPERATIONS

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. As denoted there will be two valves and one check valve on the kill line, two valves on the choke line, and two adjustable chokes on the manifold system. The BOP "stack" will consist of two BOP rams (1 pipe, 1 blind) and one annular type preventer, all rated to a minimum of 3,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling out surface casing shoe and anytime a new casing string is set..

All test pressures will be maintained for fifteen (15) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items.

1.	Annular BOP	1,500 psi
2.	Ram type BOP	3,000 psi
3.	Kill line valves	3,000 psi
4.	Choke line valves and choke manifold valves	3,000 psi
5.	Chokes	3,000 psi
6.	Casing, casinghead & weld	1,500 psi
7.	Upper kelly cock and safety valve	3,000 psi
8.	Dart valve	3,000 psi

#### 6. MUD SYSTEMS

- An air or an air/mist system may be used to drill to drill the surface hole until water influx becomes too great.
- KCL mud system will be used to drill well.
- The mud system will be monitored manually/visually.

<u>Depths</u>	Mud Weight (ppg)	Mud System
0' - 500'	8.4	Air foam mist, no pressure control
500' – 3,325'	8.6	Fresh water, rotating head and diverter
3,325' - 8,650'	8.6	Fresh water/2% KCL/KCL mud system

#### 7. BLOOIE LINE

- An automatic igniter will not be installed on blooie line. The blooie will have a contant ignition source.
- A "target tee" connection will be installed on blooie line for 90° change of directions for abrasion resistance.
- "Target tee" connections will be a minimum of 50' from wellhead.
- The blooie line discharge will be a minimum of 80' from the wellhead.

#### 8. AUXILIARY EQUIPMENT TO BE USED

- a. Kelly cock.
- b. Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string.

#### 9. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

- A drillstem test in the Wasatch Tongue is possible.
- One electric line wire-log will be run from total depth to intermediate casing.
- The gamma ray will be left on to record from total depth to intermediate casing.
- Other log curves (resistivities, porosity, and caliper) will record from total depth to intermediate casing.
- A dipmeter, percussion cores, or rotary cores may be run over selected intervals.

#### 10. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

- Expected BHP 1,500-2,000 psi (lower than normal pressure gradient).
- No abnormal temperature or pressures are anticipated.
- The formations to be penetrated do not contain known H2S gas.

#### 11. WATER SUPPLY

- No water pipelines will be laid for this well.
- No water well will be drilled for this well.
- Drilling water for this will be hauled on the road(s) shown in Attachment No. 3.
- Water will be hauled from: Water Permit # 43-10447 Section 9, Township 8 South, Range 20 East

#### APPROVAL OF OPERATIONS

#### 12. CEMENT SYSTEMS

- **Surface Cement:** 
  - Drill 17-1/2" hole to 500' and cement 13-3/8" to surface with 450 sks class "C" cement with 2% CaCl2 and 1/4 #/sk. Polyflake (volume includes 70% excess). Top out as necessary. Casing to be centralized with a total of 5 centralizers.
- **Intermediate Casing Cement:** 
  - Drill 12-1/4" hole to 3,325'±, run and cement 9-5/8" to surface.
  - Pump 20 bbls lightly weighted water spacer followed by 5 bbls fresh water. Displace with any available water.
  - Casing to be run with: a) guide shoe b) insert float c) three (3) centralizers, one on each of first 3 joints d) stop ring for plug one joint off bottom e) bottom three joints thread locked f) pump job with bottom plug only. Casing to be centralized with a total of 15 centralizers.
  - Cement to surface not required due to surface casing set deeper than normal.

					<u>Hole</u>	<u>Cement</u>
Type	Sacks	Interval	Density	Yield	<u>Volume</u>	<u>Volume</u>
Lead	388	0'-2,825'	10.5 ppg	4.14 CFS	919 <b>CF</b>	1,608 CF
Tail	254	2,825'-3,325'	15.6 ppg	1.2 CFS	174 CF	305 CF

Intermediate design volumes based on 75% excess of gauge hole.

Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7. Lead Mix:

4.14 cf/sack Slurry weight: 10.5 #/gal. Slurry yield:

26.07 gal/sack Water requirement: Compressives (a), 110°F: 72 psi after 24 hours

Class "G" Cement, 1/4 lb/sk Cellophane Flakes + 2% bwoc Calcium Chloride + 46.5% fresh water. Tail Mix:

> 1.20 cf/sack Slurry weight: 15.6 #/gal. Slurry yield:

1 hr. 5 min. (a), 110 °F. Pump Time:

Compressives @ 110 °F: 2,500 psi after 24 hours

#### c. Production Casing Cement:

- Drill 7-7/8" hole to 8,650'±, run and cement 5 1/2".
- Pump 20 bbl Mud Clean II unweighted spacer, followed by 20 Bbls fresh H20 spacer.
- Displace with 2% KCL.
- Production casing to be centralized with 30 centralizers.

					<u>Hole</u>	<u>Cement</u>
Type	Sacks	<u>Interval</u>	Density	Yield Yield	<u>Volume</u>	<u>Volume</u>
Lead	90	3,875'-4,675'	11.5 ppg	3.12 CFS	139 CF	277 CF
Tail	790	4.675-8.650	13.0 ppg	1.75 CFS	689 CF	1377 CF

Production design volumes based on 35% excess of gauge hole. Actual volumes will be calculated from caliper log to bring lead cement to 800' above top of Wasatch + 15% excess, and tail cement to top of Wasatch +15%.

Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7. Lead Mix:

> 3.12 cf/sack Slurry weight: 11.60 #/gal. Slurry vield:

Water requirement: 17.71 gal/sack

Compressives (a), 130°F: 157 psi after 24 hours

Halliburton HLC blend (Prem Plus V/JB flyash). Blend includes Class "G" cement, KCl, EX-1, Halad 322, Tail Mix:

> & HR-5. 1.75 cf/sack

Slurry weight: 13.00 #/gal. Slurry yield: Water requirement: 9.09 gal/sack


Compressives (a) 165°F: 905 psi after 24 hours

## 13. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

January 15, 2007

Starting Date:

**Duration:** 14 Days





## Ryan Energy Technologied **Planning Report**



Company: Dominion Exploration & Product

Field: Site: Well:

Uintah County, Utah **RBU 21-18F** 

**RBU 21-18F** 

Date: 8/24/2006

Time: 09:08:14

Co-ordinate(NE) Reference: Well: RBU 21-18F, True North

Vertical (TVD) Reference: Section (VS) Reference:

Est RKB 5095.0

Well (0.00N,0.00E,302.51Azi)

Plan #1

Field:

Uintah County, Utah

Utah - Natural Buttes

USA

Wellpath: Original Hole

Map System: US State Plane Coordinate System 1983

Geo Datum: GRS 1980 Sys Datum: Mean Sea Level Map Zone: Coordinate System: Utah, Central Zone

Geomagnetic Model:

Well Centre igrf2005

Site:

RBU 21-18F

Sec 18 10S, 20 E Ulntah County, Utah

Site Position: Geographic Northing:

7154290.67 ft

Latitude: Longitude:

39 56 48.070 N 109

From: **Position Uncertainty:** 

2139760.38 ft Easting:

North Reference:

43 7.580 W

0.00 ft

True

**Ground Level:** 

Well Position:

5080.00 ft

**Grid Convergence:** 

1.14 deg

Well:

**RBU 21-18F** 

0.00 ft Northing: 7154290.67 ft 0.00 ft 2139760.38 ft Easting:

Latitude: Longitude:

Slot Name:

39 56 48.070 N

+E/-W Position Uncertainty:

0.00 ft

109 43 7.580 W

Wellpath: Original Hole

+N/-S

Est RKB

Tie-on Depth: **Above System Datum:** 

**Drilled From:** 

Surface 0.00 ft

**Current Datum:** Magnetic Data:

8/23/2006

Height 5095.00 ft

Declination: Mag Dip Angle: Mean Sea Level 11.77 deg 65.91 deg

Field Strength: 52804 nT **Vertical Section:** Depth From (TVD)

Plan #1

+N/-S

+E/-W

Direction deg

ft 0.00 302.51 8650.00 0.00

Principal: Yes

Plan:

**Date Composed:** Version:

8/23/2006

Tied-to: From Surface

**Plan Section Information** 

	MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg	Target	
	0.00	0.00	302.51	0.00	0.00	0.00	0.00	0.00	0.00	0.00		· · · · · · · · · · · · · · · · · · ·
	540.00	0.00	302.51	540.00	0.00	0.00	0.00	0.00	0.00	0.00		
1	1819.65	38.39	302.51	1726.03	221.91	-348.20	3.00	3.00	0.00	302.51		
	1995.62	38.39	302.51	1863.96	280.64	-440.36	0.00	0.00	0.00	0.00	*	
	3275.29	0.00	302.51	3050.00	502.56	-788.56	3.00	-3.00	0.00	180.00	Vertical Point	
H	8875.29	0.00	302.51	8650.00	502.56	-788.56	0.00	0.00	0.00	302.51	PBHL	

Survey										
MD ft	Inci deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100f	Build t deg/100ft	Turn deg/100ft	Tool/Comment
540.00	0.00	302.51	540.00	0.00	0.00	0.00	0.00	0.00	0.00	
600.00	1.80	302.51	599.99	0.51	-0.79	0.94	3.00	3.00	0.00	
700.00	4.80	302.51	699.81	3.60	-5.65	6.70	3.00	3.00	0.00	
800.00	7.80	302.51	799.20	9.50	-14.90	17.67	3.00	3.00	0.00	
900.00	10.80	302.51	897.87	18.18	-28.53	33.83	3.00	3.00	0.00	
1000.00	13.80	302.51	995.57	29.63	-46.49	55.13	3.00	3.00	0.00	
1100.00	16.80	302.51	1092.01	43.81	-68.74	81.51	3.00	3.00	0.00	
1200.00	19.80	302.51	1186.94	60.68	-95.22	112.91	3.00	3.00	0.00	**
1300.00	22.80	302.51	1280.10	80.20	-125.85	149.23	3.00	3.00	0.00	
1400.00	25.80	302.51	1371.23	102.32	-160.55	190.38	3.00	3.00	0.00	
1500.00	28.80	302.51	1460.08	126.97	-199.22	236.24	3.00	3.00	0.00	
1600.00	31.80	302.51	1546.41	154.08	-241.76	286.69	3.00	3.00	0.00	
1700.00	34.80	302.51	1629.98	183.58	-288.06	341.58	3.00	3.00	0.00	
1800.00	37.80	302.51	1710.56	215.40	-337.98	400.78	3.00	3.00	0.00	
1819.65	38.39	302.51	1726.03	221.91	-348.20	412.90	3.00	3.00	0.00	



## Ryan Energy Technologied **Planning Report**



Company: Dominion Exploration & Product

Field: Site:

Uintah County, Utah

RBU 21-18F RBU 21-18F Well: Wellpath: Original Hole

Date: 8/24/2006 Time: 09:08:14 Co-ordinate(NE) Reference: Well: RBU 21-18F, True North

Vertical (TVD) Reference: Est RKB 5095.0 Section (VS) Reference:

Well (0.00N,0.00E,302.51Azi) Plan #1

м спряги:	Original no	ле			FR	3114		FIGIT #-I		<del></del>
Survey										
MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS dec/100ft	Build deg/100ft	Turn dec/100ft	Tool/Comment
						,				
1900.00	38.39	302.51	1789.01	248.73	-390.28	462.80	0.00	0.00	0.00	•
1995.62	38.39	302.51	1863.96	280.64	-440.36	522.18	0.00	0.00	0.00	The second secon
2000.00	38.26	302.51	1867.39	282.10	-442.64	524.90	3.00	-3.00	0.00	
2100.00	35.26	302.51	1947.50	314.26	-493.11	584.73	3.00	-3.00	0.00	
2200.00	32.26	302.51	2030.63	344.13	-539.96	640.30	3.00	-3.00	0.00	
2300.00	29.26	302.51	2116.55	371.61	-583.09	691.43	3.00	-3.00	0.00	
2400.00	26.26	302.51	2205.03	396.64	-622.36	738.00	3.00	-3.00	0.00	
2500.00	23.26	302.51	2295.83	419.14	-657.67	779.88	3.00	-3.00	0.00	
2600.00	20.26	302.51	2388.69	439.06	-688.93	816.94	3.00	-3.00	0.00	•
2700.00	17.26	302.51	2483.37	456.34	-716.04	849.10	3.00	-3.00	0.00	
0000 00	44.00	200 54	0570.00	470.04	. 200.04	070.05		0.00	0.00	
2800.00	14.26	302.51	2579.60	470.94	-738.94	876.25	3.00	-3.00	0.00	
2900.00	11.26	302.51	2677.12	482.81	-757.57	898.34	3.00	-3.00	0.00	
3000.00	8.26	302.51	2775.66	491.92	-771.86	915.28	3.00	-3.00	0.00	
3100.00	5.26	302.51	2874.96	498.24	-781.78	927.05	3.00	-3.00	0.00	
3200.00	2.26	302.51	2974.73	501.76	-787.31	933.61	3.00	-3.00	0.00	
3275.29	0.00	302.51	3050.00	502.56	-788.56	935.09	3.00	-3.00	0.00	Vertical Point
3300.00	0.00	302.51	3074.71	502.56	-788.56	935.09	0.00	0.00	0.00	V GIUCALI VIIIL
3400.00	0.00	302.51	3174.71	502.56						
3500.00	0.00	302.51	3174.71 3274.71		-788.56	935.09	0.00	0.00	0.00	
				502.56	-788.56	935.09	0.00	0.00	0.00	
3550.29	0.00	302.51	3325.00	502.56	-788.56	935.09	0.00	0.00	0.00	Intermediate
3600.00	0.00	302.51	3374.71	502.56	-788.56	935.09	0.00	0.00	0.00	
3700.00	0.00	302.51	3474.71	502.56	-788.56	935.09	0.00	0.00	0.00	
3800.00	0.00	302.51	3574.71	502.56	-788.56	935.09	0.00	0.00	0.00	
3900.00	0.00	302.51	3674.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4000.00	0.00	302.51	3774.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4100.00	0.00	302.51	3874.71	502.56	-799 FC	035.00	0.00	0.00	0.00	
4200.00					-788.56	935.09	0.00	0.00	0.00	
	0.00	302.51	3974.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4300.00	0.00	302.51	4074.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4370.29	0.00	302.51	4145.00	502.56	-788.56	935.09	0.00	0.00	0.00	Wasatch Tongue
4400.00	0.00	302.51	4174.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4500.00	0.00	302.51	4274.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4600.00	0.00	302.51	4374.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4700.00	0.00	302.51	4474.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4740.29	0.00	302.51	4515.00	502.56	-788.56	935.09	0.00	0.00	0.00	Uteland Limestone
4800.00	0.00	302.51	4574.71	502.56	-788.56	935.09	0.00	0.00	0.00	Otelanu Limestone
4000.00	0.00	200 54	4074 74							
4900.00	0.00	302.51	4674.71	502.56	-788.56	935.09	0.00	0.00	0.00	
4900.29	0.00	302.51	4675.00	502.56	-788.56	935.09	0.00	0.00	0.00	Wasatch
5000.00	0.00	302.51	4774.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5100.00	0.00	302.51	4874.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5200.00	0.00	302.51	4974.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5300.00	0.00	302.51	5074.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5400.00	0.00	302.51	5174.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5500.00	0.00	302.51	5274.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5600.00	0.00	302.51	5374.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5700.00	0.00	302.51	5474.71	502.56	-788.56	935.09	0.00	0.00	0.00	
E000 00										· ·
5800.00	0.00	302.51	5574.71	502.56	-788.56	935.09	0.00	0.00	0.00	
5810.29	0.00	302.51	5585.00	502.56	-788.56	935.09	0.00	0.00	0.00	Chapita Wells
5900.00	0.00	302.51	5674.71	502.56	-788.56	935.09	0.00	0.00	0.00	
6000.00	0.00	302.51	5774.71	502.56	-788.56	935.09	0.00	0.00	0.00	
6100.00	0.00	302.51	5874.71	502.56	-788.56	935.09	0.00	0.00	0.00	
6200.00	0.00	302 51	507 <i>A</i> 71	502 56	-788 56	035.00	0.00	0.00	0.00	
			6074.71	502.56 502.56		935.09		0.00	0.00	
	በ ለለ									
6300.00 6400.00	0.00 0.00	302.51 302.51	6174.71	502.56	-788.56	935.09	0.00 0.00	0.00	0.00	
6200.00	0.00	302.51	5974.71	502.56	-788.56 -788.56	935.09	0.00	0.00	0.00	



## Ryan Energy Technologied **Planning Report**



Company: Dominion Exploration & Product

Field:

Wellpath: Original Hole

Well:

Uintah County, Utah RBU 21-18F **RBU 21-18F** 

Date: 8/24/2006

Time: 09:08:14

Co-ordinate(NE) Reference: Well: RBU 21-18F, True North

Vertical (TVD) Reference: Est RKB 5095.0
Section (VS) Reference: Well (0.00N,0.00E,302.51Azi)

MID ft	Incl deg	Azim deg	TVD Tt	+N/-S ft	+E/-W ft	VS ft	DLS deg/100f	<b>Build</b> t deg/100f	Turn t deg/100ft	Tool/Comment
600.00	0.00	302.51	6374.71	502.56	-788.56	935.09	0.00	0.00	0.00	
6700.00	0.00	302.51	6474.71	502.56	-788.56	935.09	0.00	0.00	0.00	
6800.00	0.00	302.51	6574.71	502.56	-788.56	935.09	0.00	0.00	0.00	
6900.00	0.00	302.51	6674.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7000.00	0.00	302.51	6774.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7060.29	0.00	302.51	6835.00	502.56	-788.56	935.09	0.00	0.00	0.00	Uteland Buttes
7100.00	0.00	302.51	6874.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7200.00	0.00	302.51	6974.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7300.00	0.00	302.51	7074.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7400.00	0.00	302.51	7174.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7500.00	0.00	302.51	7274.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7600.00	0.00	302.51	7374.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7700.00	0.00	302.51	7474.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7800.00	0.00	302.51	7574.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7900.00	0.00	302.51	7674.71	502.56	-788.56	935.09	0.00	0.00	0.00	
7950.29	0.00	302.51	7725.00	502.56	-788.56	935.09	0.00	0.00	0.00	Mesaverde
8000.00	0.00	302.51	7774.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8100.00	0.00	302.51	7874.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8200.00	0.00	302.51	7974.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8300.00	0.00	302.51	8074.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8400.00	0.00	302.51	8174.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8500.00	0.00	302.51	8274.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8600.00	0.00	302.51	8374.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8700.00	0.00	302.51	8474.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8800.00	0.00	302.51	8574.71	502.56	-788.56	935.09	0.00	0.00	0.00	
8875.29	0.00	302.51	8650.00	502.56	-788.56	935.09	0.00	0.00	0.00	PBHL

Tarcet	•

Name	Description Dip.	Dir.	TVD ft	+N/-S ft	+E/-W	Map Northing ft	Map Easting ft	< Latitude> Deg Min Sec	< Longitude> Deg Min Sec
Vertical Point -Plan hit target			3050.00	502.56	-788.56	7154777.432	2138961.97	39 56 53.037 N	109 43 17.706 W
PBHL -Plan hit target			8650.00	502.56	-788.56	7154777.432	2138961.97	39 56 53.037 N	109 43 17.706 W

## **Casing Points**

MD ft	TVD ft	Diameter in	Hole Size in	Name	
3550.29	3325.00	9.625	9.625	Intermediate	

#### **Formations**

MD ft	TVD ft	Formations	Lithology	Dip Angle deg	Dip Direction deg
4370.29	4145.00	Wasatch Tongue		0.00	0.00
4740.29	4515.00	Uteland Limestone		0.00	0.00
4900.29	4675.00	Wasatch		0.00	0.00
5810.29	5585.00	Chapita Wells		0.00	0.00
7060.29	6835.00	Uteland Buttes		0.00	0.00
7950.29	7725.00	Mesaverde		0.00	0.00

## SURFACE USE PLAN

## CONDITIONS OF APPROVAL

## Attachment for Permit to Drill

Name of Operator:

**Dominion Exploration & Production** 

Address:

14000 Quail Springs Parkway, Suite 600

Oklahoma City, OK 73134

Well Location:

**RBU 21-18F** 

SHL: 2379' FSL & 834' FWL Section 18-10S-20E BHL: 2450' FNL & 50' FWL Section 18-10S-20E

Uintah County, UT

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

The BLM onsite inspection for the referenced well was conducted on Thursday, August 10, 2006 at approximately 10:42 am. In attendance at the onsite inspection were the following individuals:

Karl Wright **Brandon McDonald**  Nat. Res. Prot. Spec. Wildlife Biologist

Bureau of Land Management - Vernal

Ken Secrest

Field Foreman

Bureau of Land Management - Vernal

Dominion E & P, Inc.

Brandon Bowthorpe

Surveyor Foreman

Uintah Engineering & Land Surveying

Billy McClure Randy Jackson

Foreman

LaRose Construction **Jackson Construction** 

Don Hamilton

Agent

Buys & Associates, Inc.

#### 1. **Existing Roads:**

- No upgrades to existing roads and no new roads are proposed at this time since access will a. utilize the existing road to the existing well site.
- The proposed well site is located approximately 10.02 miles south of Ouray, UT. b.
- Directions to the proposed well site have been attached at the end of Exhibit B. c.
- The use of roads under State and County Road Department maintenance are necessary to d. access the River Bend Unit. However, an encroachment permit is not anticipated since no upgrades to the State or County Road system are proposed at this time.
- All existing roads will be maintained and kept in good repair during all phases of operation. e.
- Vehicle operators will obey posted speed restrictions and observe safe speeds commensurate e. with road and weather conditions.
- Since no improvements are anticipated to any State, County, Tribal or BLM access roads no f. topsoil striping will occur.
- An off-lease federal right-of-way is not anticipated for the access road or utility corridor g. since both are located within the existing River Bend Unit boundary and both utilize entirely existing disturbance.

#### 2. Planned Access Roads:

- a. The proposed well utilizes the existing wellsite RBU 12-18F with no new access proposed.
- b. The operator will be responsible for all maintenance of the existing access road including drainage structures.

## 3. <u>Location of Existing Wells</u>:

Exhibit B has a map reflecting these wells within a one mile radius of the proposed well.

#### 4. Location of Production Facilities:

- a. All permanent structures will be painted a flat, non-reflective Desert Brown or Carlsbad Canyon to match the standard environmental colors. All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.
- Site security guidelines identified in 43 CFR 3163.7-5 and Onshore Oil and Gas Order No. 3 will be adhered to.
- c. A gas meter run will be constructed and located on lease within 500 feet of the wellhead. Meter runs will be housed and/or fenced. All gas production and measurement shall comply with the provisions of 43 CFR 3162. 7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.
- d. A tank battery will be constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain the storage capacity of the largest tank. All loading lines and valves will be placed inside the berm surrounding the tank battery. All liquid hydrocarbons production and measurement shall conform to the provisions of 43 CFR 3162.7-3 and Onshore Oil and Gas Order No. 4 and Onshore Oil and Gas Order No. 5 for natural gas production and measurement.
- e. Any necessary pits will be properly fenced to prevent any wildlife and livestock entry.
- f. All access roads will be maintained as necessary to prevent erosion and accommodate year-round traffic. The road will be maintained in a safe useable condition.
- g. The site will require periodic maintenance to ensure that drainages are kept open and free of debris, ice, and snow, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.
- f. No new pipeline corridors are proposed at this time since gas transportation will utilize the existing pipeline network to the existing well site.
- g. The existing pipeline will be upgrade to 10" or less, as needed, from the proposed well to the existing Compressor #4 to provide additional production transportation capacity from the proposed 20 acre in-field wells.
- h. The upgraded gas pipeline will be a 10" or less steel surface line within a 20' wide utility corridor. The use of the proposed well site and access roads will facilitate the staging of the pipeline construction.
- Dominion intends on installing the upgraded pipeline on the surface by welding many joints

into long lengths, dragging the long lengths into position and then completing a final welding pass to join the long lengths together. Dominion intends on connecting the pipeline together utilizing conventional welding technology.

## 5. <u>Location and Type of Water Supply:</u>

a. The location and type of water supply has been addressed as number 11 within the previous drilling plan information.

#### 6. Source of Construction Material:

- a. The use of materials will conform to 43 CFR 3610.2-3.
- b. No construction materials will be removed from Ute Tribal or BLM lands.
- c. If any gravel is used, it will be obtained from a state approved gravel pit.

#### 7. <u>Methods of Handling Waste Disposal:</u>

- a. All wastes associated with this application will be contained and disposed of utilizing approved facilities.
- b. Drill cuttings will be contained and buried on site.
- c. The reserve pit will be located outboard of the location and along the northeast side of the pad.
- d. The reserve pit will be constructed so as not to leak, break, or allow any discharge.
- e. The reserve pit will be lined with 16 mil minimum thickness plastic nylon reinforced liner material. The liner will overlay a felt liner pad only if rock is encountered during excavation. The pit liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. Pit walls will be sloped no greater than 2:1. A minimum 2-foot freeboard will be maintained in the pit at all times during the drilling and completion operation.
- f. The reserve pit has been located in cut material. Three sides of the reserve pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. After the reserve pit has dried, all areas not needed for production will be rehabilitated.
- g. No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completion of the well.
- h. Trash will be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations. The contents of the trash container will be hauled off periodically to the approved Uintah County Landfill near Vernal, Utah.

- i. Produced fluids from the well other than water will be produced into a test tank until such time as construction of production facilities is completed. Any spills of oil, gas, salt water or other produced fluids will be cleaned up and removed.
- j. After initial clean-up, a 400 bbl tank will be installed to contain produced waste water. This water will be transported from the tank to an approved Dominion disposal well for disposal.
- k. Produced water from the production well will be disposed of at the RBU 13-11F or RBU 16-19F disposal wells in accordance with Onshore Order #7.
- 1. Any salts and/or chemicals, which are an integral part of the drilling system, will be disposed of in the same manner as the drilling fluid.
- m. Sanitary facilities will be on site at all times during operations. Sewage will be placed in a portable chemical toilet and the toilet replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

## 8. Ancillary Facilities:

a. Garbage Containers and Portable Toilets are the only ancillary facilities proposed in this application.

## 9. Well Site Layout: (See Exhibit B)

- a. The well will be properly identified in accordance with 43 CFR 3162.6.
- b. Access to the well pad will be from the northeast.
- c. The pad and road designs are consistent with BLM specification
- d. A pre-construction meeting with responsible company representative, contractors and the BLM will be conducted at the project site prior to commencement of surface-disturbing activities. The pad and road will be construction-staked prior to this meeting.
- e. The pad has been staked at its maximum size of 355' X 200'; however it will be constructed smaller if possible, depending upon rig availability. Should the layout change, this application will be amended and approved utilizing a sundry notice.
- f. All surface disturbing activities, will be supervised by a qualified, responsible company representative who is aware of the terms and conditions of the APD and specifications in the approved plans.
- g. All cut and fill slopes will be such that stability can be maintained for the life of the activity.
- h. Diversion ditches will be constructed as shown around the well site to prevent surface waters form entering the well site area.
- The site surface will be graded to drain away from the pit to avoid pit spillage during large storm events.
- j. The stockpiled topsoil (first 6 inches or maximum available) will be stored in a windrow on the uphill side of the location to prevent any possible contamination. All topsoil will be stockpiled for reclamation in such a way as to prevent soil loss and contamination.

- k. Pits will remain fenced until site cleanup.
- 1. The blooie line will be located at least 100 feet from the well head.
- m. Water injection may be implemented if necessary to minimize the amount of fugitive dust.

## 10. Plans for Restoration of the Surface (Interim Reclamation and Final Reclamation):

- a. Site reclamation for a producing well will be accomplished for portions of the site not required for the continued operation of the well.
- b. Upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1. Once the reserve pit is dry, the plastic nylon reinforced liner shall be torn and perforated before backfilling of the reserve pit. The reserve pit and that portion of the location not needed for production facilities/operations will be re-contoured to the approximate natural contours.
- c. Following BLM published Best Management Practices the interim reclamation will be completed within 90 days of completion of the well to reestablish vegetation, reduce dust and erosion and compliment the visual resources of the area.
  - a. All equipment and debris will be removed from the area proposed for interim reclamation and the pit area will be backfilled and re-contoured.
  - b. The area outside of the rig anchors and other disturbed areas not needed for the operation of the well will be re-contoured to blend with the surrounding area and reseeded at 12 lbs /acre with the following native grass seeds:

1. Crested Wheat Grass

(4 lbs / acre)

2. Needle and Thread Grass

(4 lbs / acre)

3. Rice Grass

(4 lbs / acre)

- c. Reclaimed areas receiving incidental disturbance during the life of the producing well will be re-contoured and reseeded as soon as practical.
- d. The Operator will control noxious weeds along access road use authorizations, pipeline route authorizations, well sites, or other applicable facilities by spraying or mechanical removal. A list of noxious weeds may be obtained from the BLM or the appropriate County Extension Office. On BLM administered land, it is required that a Pesticide Use Proposal be submitted and approved prior to the application of herbicides, pesticides or possibly hazardous chemicals.
- e. Prior to final abandonment of the site, all disturbed areas, including the access road, will be scarified and left with a rough surface. The site will then be seeded and/or planted as prescribed by the BLM. The BLM recommended seed mix will be detailed within their approval documents.

## 11. Surface and Mineral Ownership:

- a. Surface Ownership Federal under the management of the Bureau of Land Management Vernal Field Office, 170 South 500 East, Vernal, Utah 84078; 435-781-4400.
- b. Mineral Ownership Federal under the management of the Bureau of Land Management Vernal Field Office, 170 South 500 East, Vernal, Utah 84078; 435-781-4400.

#### 12. Other Information:

- a. AIA Archaeological has conducted a Class III archeological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by AIA Archaeological.
- b. Alden Hamblin has conducted a paleontological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by Alden Hamblin.
- c. Our understanding of the results of the onsite inspection are:
  - a. No Threatened and Endangered flora and fauna species were found during the onsite inspection.
  - No drainage crossings that require additional State or Federal approval are being crossed.
  - c. A pipeline upgrade is proposed with this application.

#### 13. Operator's Representative and Certification

Title	Name	Office Phone
Company Representative (Roosevelt)	Ken Secrest	1-435-722-4521
Company Representative (Oklahoma)	Carla Christian	1-405-749-5263
Agent for Dominion	Don Hamilton	1-435-637-4075

### Certification:


I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exists; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Dominion Exploration & Production, Inc. and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided under Dominion's BLM bond. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.


Signature: Don Hamilton Date: 8-31-06

## DOMINION EXPLR. & PROD., INC. RBU #21-18F SECTION 18, T10S, R20E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 9.1 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 2.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE WEST; TURN RIGHT AND PROCEED IN A WESTERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN RIGHT AND PROCEED IN A NORTHERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 2.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN RIGHT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE WEST; PROCEED IN A WESTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN LEFT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE EXISTING #12-18F AND THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 48.3 MILES.





## DOMINION EXPLR. & PROD., INC.

RBU #21-18F LOCATED IN UINTAH COUNTY, UTAH SECTION 18, T10S, R20E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHWESTERLY



PHOTO: VIEW OF EXISTING ACCESS

**CAMERA ANGLE: NORTHWESTERLY** 



Uintah Engineering & Land Surveying


85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com


LOCATION PHOTOS


O7 17 O6


РНОТО


TAKEN BY: B.B. DRAWN BY: B.C. REVISED: 00-00-00












APD RECEIVED: 08/31/2006	API NO. ASSIGNED: 43-047-38554			
WELL NAME: RBU 21-18F  OPERATOR: DOMINION EXPL & PROD ( N1095 )  CONTACT: DON HAMILTON	PHONE NUMBER: 405-749-5263			
PROPOSED LOCATION:	INSPECT LOCATN BY: / /			
NWSW 18 100S 200E SURFACE: 2379 FSL 0834 FWL	Tech Review Initials Date			
BOTTOM: 2450 FNL 0050 FWL	Engineering			
COUNTY: UINTAH LATITUDE: 39.94669 LONGITUDE: -109.7181	Geology			
UTM SURF EASTINGS: 609514 NORTHINGS: 4422417	Surface			
FIELD NAME: NATURAL BUTTES (630)  LEASE TYPE: 1 - Federal  LEASE NUMBER: U013769-A  SURFACE OWNER: 1 - Federal	PROPOSED FORMATION: MVRD COALBED METHANE WELL? NO			
Plat Bond: Fed[1] Ind[] Sta[] Fee[] (No. WY 3322 ) Potash (Y/N)  V Oil Shale 190-5 (B) or 190-3 or 190-13 Water Permit (No. 43-10447)	R649-2-3.  E: RIVER BEND  R649-3-2. General Siting: 460 From Qtr/Qtr & 920' Between Wells  R649-3-3. Exception  Drilling Unit Board Cause No: 259-01 Eff Date: 8-14-04 Siting: Strends Ebya-311  R649-3-11. Directional Drill			
STIPULATIONS: 1- Ledi 12 (1851-14)  Z-OIL SHALE				



## **United States Department of the Interior**

## BUREAU OF LAND MANAGEMENT Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

September 19, 2006

#### Memorandum

To:

Assistant District Manager Minerals, Vernal District

From:

Michael Coulthard, Petroleum Engineer

Subject:

2006 Plan of Development River Bend Unit Uintah County,

Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2006 within the River Bend Unit, Uintah County, Utah.

API#

WELL NAME

LOCATION

(Proposed PZ MesaVerde)

43-047-38582 RBU 17-10E Sec 10 T10S R19E 0477 FNL 1390 FEL BHL Sec 10 T10S R19E 1000 FNL 0465 FEL

43-047-38584 RBU 27-10E Sec 10 T10S R19E 0723 FSL 2350 FEL BHL Sec 10 T10S R19E 1350 FSL 2500 FEL

43-047-38585 RBU 26-10E Sec 10 T10S R19E 1995 FSL 1184 FEL BHL Sec 10 T10S R19E 2250 FSL 2100 FEL

43-047-38586 RBU 25-10E Sec 10 T10S R19E 2013 FSL 1160 FEL BHL Sec 10 T10S R19E 1450 FSL 0200 FEL

43-047-38587 RBU 23-10E Sec 10 T10S R19E 2007 FSL 1168 FEL BHL Sec 10 T10S R19E 2350 FNL 1350 FEL

43-047-38588 RBU 22-10E Sec 10 T10S R19E 2064 FNL 1241 FWL BHL Sec 10 T10S R19E 2400 FNL 2300 FWL

43-047-38543 RBU 28-18F Sec 13 T10S R19E 1640 FSL 0901 FEL BHL Sec 18 T20S R20E 1600 FSL 0100 FWL

43-047-38544 RBU 18-24E Sec 13 T10S R19E 0143 FSL 1844 FEL

#### BHL Sec 24 T10S R19E 0550 FNL 1550 FEL

Page 2

- 43-047-38545 RBU 19-24E Sec 13 T10S R19E 0159 FSL 1855 FEL BHL Sec 24 T10S R19E 0150 FNL 2550 FWL
- 43-047-38546 RBU 25-13E Sec 13 T10S R19E 2418 FSL 2023 FEL BHL Sec 13 T10S R19E 2700 FNL 1050 FEL
- 43-047-38547 RBU 31-13E Sec 13 T10S R19E 2433 FSL 2036 FEL BHL Sec 13 T10S R19E 1350 FSL 2400 FEL
- 43-047-38589 RBU 21-14E Sec 14 T10S R19E 2240 FSL 0210 FWL BHL Sec 14 T10S R19E 2500 FNL 0050 FWL
- 43-047-38590 RBU 27-14E Sec 14 T10S R19E 2230 FSL 0209 FWL BHL Sec 14 T10S R19E 2550 FSL 1300 FWL
- 43-047-38592 RBU 24-14E Sec 14 T10S R19E 1257 FNL 0432 FEL BHL Sec 14 T10S R19E 1300 FNL 1250 FEL
- 43-047-38593 RBU 23-14E Sec 14 T10S R19E 2375 FNL 2360 FWL BHL Sec 14 T10S R19E 1450 FNL 2350 FEL
- 43-047-38595 RBU 31-10E Sec 15 T10S R19E 0305 FNL 1324 FEL BHL Sec 10 T10S R19E 0200 FSL 1450 FEL
- 43-047-38596 RBU 17-15E Sec 15 T10S R19E 0320 FNL 1324 FEL BHL Sec 15 T10S R19E 1350 FNL 1200 FEL
- 43-047-38597 RBU 18-15E Sec 15 T10S R19E 0125 FNL 1570 FWL BHL Sec 15 T10S R19E 1000 FNL 2100 FWL
- 43-047-38598 RBU 20-14E Sec 15 T10S R19E 1821 FNL 0532 FEL BHL Sec 14 T10S R19E 1100 FNL 0100 FWL
- 43-047-38554 RBU 21-18F Sec 18 T10S R20E 2379 FSL 0834 FWL BHL Sec 18 T10S R20E 2450 FNL 0050 FWL
- 43-047-38555 RBU 27-18F Sec 18 T10S R20E 0902 FSL 2032 FWL BHL Sec 18 T10S R20E 1500 FSL 2700 FWL
- 43-047-38556 RBU 27-18F2 Sec 18 T10S R20E 0888 FSL 2005 FWL BHL Sec 18 T10S R20E 1500 FSL 1300 FWL
- 43-047-38557 RBU 30-18F Sec 18 T10S R20E 0897 FSL 2023 FWL BHL Sec 18 T10S R20E 0250 FSL 2800 FWL
- 43-047-38558 RBU 29-18F Sec 18 T10S R20E 0884 FSL 1996 FWL BHL Sec 18 T10S R20E 0150 FSL 1200 FWL
- 43-047-28549 RBU 17-24E Sec 19 T10S R20E 0703 FNL 0546 FWL BHL Sec 24 T10S R19E 0100 FNL 0150 FEL
- 43-047-38550 RBU 18-19F Sec 19 T10S R20E 0650 FNL 3147 FWL BHL Sec 19 T10S R20E 0050 FNL 2400 FEL

Page 3

- 43-047-38551 RBU 19-19F Sec 19 T10S R20E 0730 FNL 0558 FWL BHL Sec 19 T10S R20E 1400 FNL 1500 FWL
- 43-047-38552 RBU 20-19F Sec 19 T10S R20E 0721 FNL 0554 FWL BHL Sec 19 T10S R20E 1700 FNL 0200 FWL
- 43-047-38553 RBU 23-19F Sec 19 T10S R20E 0654 FNL 3156 FWL BHL Sec 19 T10S R20E 1450 FNL 2850 FEL
- 43-047-38548 RBU 32-13E Sec 13 T10S R19E 1624 FSL 0913 FEL BHL Sec 13 T10S R19E 1050 FSL 1550 FEL
- 43-047-38583 RBU 18-10E Sec 10 T10S R19E 0471 FNL 1409 FEL BHL Sec 10 T10S R19E 1350 FNL 1300 FEL
- 43-047-38591 RBU 25-14E Sec 14 T10S R19E 1380 FSL 0721 FEL BHL Sec 14 T10S R19E 2300 FSL 1250 FEL
- 43-047-38594 RBU 30-10E Sec 15 T10S R19E 0123 FNL 1590 FWL BHL Sec 10 T10S R19E 0300 FSL 2400 FWL

Our records indicate the RBU 25-10E is closer than 460 feet from the River Bend Unit boundary.

We have no objections to permitting the wells so long as the unit operator receives an exception to the locating and siting requirements of the State of Utah (R649-3-2).

/s/ Michael L. Coulthard

bcc: File - River Bend Unit

Division of Oil Gas and Mining



State of Utah

## Department of Natural Resources

MICHAEL R. STYLER Executive Director

Division of Oil, Gas & Mining

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR. Governor

GARY R. HERBERT Lieutenant Governor

September 25, 2006

Dominion Exploration & Production, Inc. 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134

Re: River Bend Unit 21-18F Well, Surface Location 2379' FSL, 834' FWL, NW SW, Sec. 18, T. 10 South, R. 20 East, Bottom Location 2450' FNL, 50' FWL, SW NW, Sec. 18, T. 10 South, R. 20 East, Uintah County, Utah

#### Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann.§ 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38554.

Sincerely,

Gil Hunt

Associate Director

Mu XI

pab

**Enclosures** 

cc:

**Uintah County Assessor** 

Bureau of Land Management, Vernal District Office

Operator: Dominion Exploration & Production, Inc.					
Well Name & Number	end Unit 21-18F				
API Number:	43-047-38554				
Lease:	U01376				
Surface Location: <u>NW SW</u>	Sec. 18	<b>T.</b> <u>10 South</u>	<b>R.</b> 20 East		
Bottom Location: SW NW	Sec. 18	T. 10 South	<b>R.</b> 20 East		

## **Conditions of Approval**

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

## 2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

Contact Dan Jarvis at (801) 538-5338

## 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

- 4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.
- 5. In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.
- 6 In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

Form 3160-5 (August, 1999)

# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

STATES FORM APPROVED
F THE INTERIOR OMB No. 1004-0135
D MANAGEMENT Expires: November 30, 20

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

Expires: November 30, 2000	
5. Lease Serial No.	
U-013769-A	-
6. If Indian, Allottee or Tribe Name	

abandoned well. Use Form 3160-3 (APD) for such proposals.				
SUBMITIN TRIPLICATE - Other Instructions on reverse side		7. If Unit or CA/Ag	reement, Name and/	or No.
1. Type of Well		River Bend	Unit	
Oil Well X Gas Well Other	TIAI 🔡	8. Well Name and I	No.	
2. Name of Operator	* ***	RBU 21-	18F	
Dominion Exploration & Production, Inc.		9. API Well No.		
3a. Address Suite 600 3b. Phone No. (inclu		43-047-38554		
14000 Quail Springs Parkway, OKC, OK 73134 (405) 749-13	00	· ·	or Exploratory Area	
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)		Natural E		
2,379' FSL & 834' FWL, NW SW, Section 18-10S-20E 2,450' FNL & 50' FWL, SW NW, Section 18-10S-20E		11. County or Paris Uintah, U		
12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF N	OTICE, REPO	ORT OR OTHE	R DATA	
TYPE OF SUBMISSION TYPE	OF ACTION			
X Notice of Intent Acidize Deepen	Production (St	tart/Resume)	Vater Shut-Off	
Altering Casing Fracture Treat	Reclamation		Well Integrity	
Subsequent Report Casing Repair New Construction	Recomplete		Other	
Change Plans Plug and Abandon	Temporarily A		ing Plan	
Final Abandonment Notice Convert to Injection Plug Back	Water Disposa	<u></u>		
Attach the Bond under which the work will be performed or provide the Bond No. on file with following completion of the involved operations. If the operation results in a multiple completion testing has been completed. Final Abandonment Notices shall be filed only after all required determined that the site is ready for final inspection.)  Please find attached a new drilling plan. Previous plan submitted plan shows measured depth.  Oil,	n or recompletion in nents, including rec	in a new interval, a lamation, have been	Form 3160-4 shall be completed and the	e filed once operator has
14. I hereby certify that the foregoing is true and correct Name (Printed/Typed)	1			
Keri Pfeifer	Title	Associate F	Regulatory Spe	cialist
Signature Kerri Pleiber	Date	11/06/2006	A. D. W.	
PRINTED TO THE TOTAL THE STATE OF THE STATE	arojancje)			
Approved by	Title		Date	4
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office			

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the

United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED NOV 1 6 2006

### **APPROVAL OF OPERATIONS**

#### **Attachment for Permit to Drill**

Name of Operator:

Dominion Exploration & Production

Address:

14000 Quail Springs Parkway, Suite 600

Oklahoma City, OK 73134

Well Location:

RBU 21-18F

SHL: 2379' FSL & 834' FWL Section 18-10S-20E

BHL: 2450' FNL & 50' FWL Section 18-10S-20E

Uintah County, UT

1. GEOLOGIC SURFACE FORMATION

Uintah

#### 2. <u>ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS</u>

<u>Formation</u>	<u>Depth</u> .
Wasatch Tongue	4,371
Uteland Limestone	4,740'
Wasatch	4,900'
Chapita Wells	5,810'
Uteland Buttes	7,060'
Mesaverde	7,950'

#### 3. ESTIMATED DEPTHS OF ANTICIPATED WATER. OIL, GAS OR MINERALS

Formation	<u>Depth</u>	<u>Type</u>
Wasatch Tongue	4,371'	Oil
Uteland Limestone	4,740'	Oil
Wasatch	4,900'	Gas
Chapita Wells	5,810'	Gas
Uteland Buttes	7,060'	Gas
Mesaverde	7,950'	Gas

### 4. PROPOSED CASING PROGRAM

All casing used to drill this well will be new casing.

<u>Type</u>	Size	Weight	Grade	Conn.	<u>Top</u>	<u>Bottom</u>	<u>Hole</u>
Surface	13-3/8"	48.0 ppf	H-40	STC	0,	500'	17-1/2"
Intermediate	9-5/8"	36.0 ppf	J-55	STC	0,	3,550'	12-1/4"
Production	5-1/2"	17.0 ppf	MAV-80	LTC	0'	8,875'	7-7/8"

## 5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

Surface hole: No BOPE will be utilized.

Intermediate hole: To be drilled using a diverter stack with rotating head to divert flow from rig floor.

<u>Production hole</u>: Prior to drilling out the intermediate casing shoe, 3,000 psi or greater BOP equipment will be installed. The pipe rams will be operated at least once per day from surface to total depth. The blind rams will be tested once per day from surface to total depth if operations permit.

#### APPROVAL OF OPERATIONS

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. As denoted there will be two valves and one check valve on the kill line, two valves on the choke line, and two adjustable chokes on the manifold system. The BOP "stack" will consist of two BOP rams (1 pipe, 1 blind) and one annular type preventer, all rated to a minimum of 3,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling out surface casing shoe and anytime a new casing string is set. All test pressures will be maintained for fifteen (15) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items.

1.	Annular BOP	1,500 psi
2.	Ram type BOP	3,000 psi
3.	Kill line valves	3,000 psi
4.	Choke line valves and choke manifold valves	3,000 psi
5.	Chokes	3,000 psi
6.	Casing, casinghead & weld	1,500 psi
7.	Upper kelly cock and safety valve	3,000 psi
8.	Dart valve	3,000 psi

#### 6. MUD SYSTEMS

- An air or an air/mist system may be used to drill to drill the surface hole until water influx becomes too great.
- KCL mud system will be used to drill well.
- The mud system will be monitored manually/visually.

<u>Depths</u>	Mud Weight (ppg)	Mud System
0'-500'	8.4	Air foam mist, no pressure control
500' - 3,550'	8.6	Fresh water, rotating head and diverter
3,550' - 8,875'	8.6	Fresh water/2% KCL/KCL mud system

### 7. BLOOIE LINE

- An automatic igniter will not be installed on blooie line. The blooie will have a contant ignition source.
- A "target tee" connection will be installed on blooie line for 90° change of directions for abrasion resistance.
- "Target tee" connections will be a minimum of 50' from wellhead.
- The blooie line discharge will be a minimum of 80' from the wellhead.

#### 8. <u>AUXILIARY EQUIPMENT TO BE USED</u>

- a. Kelly cock.
- b. Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string.

#### 9. TESTING. LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

- A drillstem test in the Wasatch Tongue is possible.
- One electric line wire-log will be run from total depth to intermediate casing.
- The gamma ray will be left on to record from total depth to intermediate casing.
- Other log curves (resistivities, porosity, and caliper) will record from total depth to intermediate casing.
- A dipmeter, percussion cores, or rotary cores may be run over selected intervals.

#### 10. <u>ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED</u>

- Expected BHP 1,500–2,000 psi (lower than normal pressure gradient).
- No abnormal temperature or pressures are anticipated.
- The formations to be penetrated do not contain known H2S gas.

#### 11. WATER SUPPLY

- No water pipelines will be laid for this well.
- No water well will be drilled for this well.
- Drilling water for this will be hauled on the road(s) shown in Attachment No. 3.
- Water will be hauled from: Water Permit # 43-10447 Section 9, Township 8 South, Range 20 East

#### **APPROVAL OF OPERATIONS**

#### 12. CEMENT SYSTEMS

- a. Surface Cement:
  - Drill 17-½" hole to 500' and cement 13-3/8" to surface with 450 sks class "C" cement with 2% CaCl<sub>2</sub> and 1/4 #/sk. Polyflake (volume includes 70% excess). Top out as necessary. Casing to be centralized with a total of 5 centralizers.
- b. Intermediate Casing Cement:
  - Drill 12-1/4" hole to 3,550'±, run and cement 9-5/8" to surface.
  - Pump 20 bbls lightly weighted water spacer followed by 5 bbls fresh water. Displace with any available water.
  - Casing to be run with: a) guide shoe b) insert float c) three (3) centralizers, one on each of first 3 joints d) stop ring for plug one joint off bottom e) bottom three joints thread locked f) pump job with bottom plug only. Casing to be centralized with a total of 15 centralizers.
  - Cement to surface not required due to surface casing set deeper than normal.

					<u>Hole</u>	<u>Cement</u>
<u>Type</u>	<u>Sacks</u>	<u>Interval</u>	<b>Density</b>	<u>Yield</u>	<u>Volume</u>	<u>Volume</u>
Lead	420	0'-3,050	10.5 ppg	4.14 CFS	993 CF	1,738 CF
Tail	254	3,050'-3,550'	15.6 ppg	1.2 CFS	174 CF	304 CF

Intermediate design volumes based on 75% excess of gauge hole.

Lead Mix: Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7.

Slurry yield: 4.14 cf/sack Slurry weight: 10.5 #/gal.

Water requirement: 26.07 gal/sack Compressives @ 110°F: 72 psi after 24 hours

Tail Mix: Class "G" Cement, 1/4 lb/sk Cellophane Flakes + 2% bwoc Calcium Chloride + 46.5% fresh water.

Slurry yield: 1.20 cf/sack Slurry weight: 15.6 #/gal.

Pump Time: 1 hr. 5 min. @ 110 °F.

Compressives (a) 110 °F: 2,500 psi after 24 hours

- c. Production Casing Cement:
  - Drill 7-7/8" hole to 8,875'±, run and cement 5 1/2".
  - Pump 20 bb! Mud Clean II unweighted spacer, followed by 20 Bbls fresh H20 spacer.
  - Displace with 2% KCL.
  - Production casing to be centralized with 30 centralizers.

					<u>Hole</u>	<u>Cement</u>
<u>Type</u>	<u>Sacks</u>	Interval	<b>Density</b>	<u>Yield</u>	<u>Volume</u>	<u>Volume</u>
Lead	90	4,100-4,900'	11.5 ppg	3.12 CFS	139 CF	277 CF
Tail	790	4,900-8,875	13.0 ppg	1.75 CFS	689 CF	1377 CF

Production design volumes based on 35% excess of gauge hole. Actual volumes will be calculated from caliper log to bring lead cement to 800' above top of Wasatch + 15% excess, and tail cement to top of Wasatch +15%.

Lead Mix: Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7.

Slurry yield: 3.12 cf/sack Slurry weight: 11.60 #/gal.

Water requirement: 17.71 gal/sack
Compressives (a), 130°F: 157 psi after 24 hours

Tail Mix: Halliburton HLC blend (Prem Plus V/JB flyash). Blend includes Class "G" cement, KCl, EX-1, Halad 322,

& HR-5.

Slurry yield: 1.75 cf/sack Slurry weight: 13.00 #/gal. Water requirement: 9.09 gal/sack

Compressives @ 165°F: 905 psi after 24 hours

13. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: January 15, 2007

Duration: 14 Days

Form 3160-5 (August, 1999),

# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM	A AF	PPRO	VE	D
OMB	No.	1004-	013	5

BUREAU OF	Expires: November 30, 2000				
	5	5. Lease Serial No.			
SUNDRY NOTICES		U-013769-A			
Do not use this form for	[6	6. If Indian, Allottee or Tribe Name			
abandoned well. Use Fo	rm 3160-3 (APD) for	such proposale			
SUBMITINTRIPLICAT			VEL	If Unit or CA/Agreement, Name and/or No.	
. Type of Well				River Bend Unit	
Oil Well X Gas Well	Other	<b>NOV</b> - 9 2	2006	8. Well Name and No.	
2. Name of Operator				RBU 21-18F	
Dominion Exploration & Production,	Inc.	<b>BLM VERNAL</b>	, UTAH	9. API Well No.	
Ba. Address Suite 600		3b. Phone No. (include are	ea code)	43-047-38554	
14000 Quail Springs Parkway, OKC,	OK 73134	(405) 749-1300	1	10. Field and Pool, or Exploratory Area	
Location of Well (Footage, Sec., T., R., M., or S	urvey Description)			Natural Buttes	
2,379' FSL & 834' FWL, NW SW, Se	ction 18-10S-20E		Ī	11. County or Parish, State	
2,450' FNL & 50' FWL, SW NW, Sec				Uintah, UT	
12. CHECK APPROPRIATE BO	X(ES) TO INDICAT	E NATURE OF NOT	ICE, REPO	RT OR OTHER DATA	
TYPE OF SUBMISSION		TYPE OF	ACTION		
X Notice of Intent	Acidize	Deepen	Production (Sta	art/Resume) Water Shut-Off	
٦ (	Altering Casing	Fracture Treat	Reclamation	Weil Integrity	
Subsequent Report	Casing Repair	New Construction	Recomplete	X Other	
	Change Plans	Plug and Abandon	Temporarily Ab	pandon Drilling Plan	
Final Abandonment Notice	Convert to Injection	( ' <del> </del>	Water Disposal		
	(alando all andianat de	talla including antimated sta	rting data of an	ny proposed work and approximate duration thereof.	
If the proposal is to deepen directionally or r Attach the Bond under which the work will following completion of the involved operatic testing has been completed. Final Aband determined that the site is ready for final insp	ecomplete horizontally. givibe performed or provide the ons. If the operation results onment Notices shall be filed section.)	e subsurface locations and re Bond No. on file with BLM in a multiple completion or r d only after all requirements	measured and /BIA. Require ecompletion ir , including recla	true vertical depths of all pertinent markers and zones. ed subsequent reports shall be filed within 30 davs n a new interval. a Form 3160-4 shall be filed once amation, have been completed and the operator has	
Please find attached a new dri	illing plan. Previous	s plan submitted with	n APD sho	wed formation tops at TVD, the corrected	
plan shows measured depth.				VERNAL DIST. DEC. 0 4 2000	
				ENG.	
	•			GEOL.	
				E.S	
				PET	
				I DI.	
14. I hereby certify that the foregoing is true and c	correct			A.M.	
Name (Printed/Typed)			T::-1	Accesiate Regulator: Specialist	
Keri Pfeifer			Title	Associate Regulatory Specialist	
Signature Keri Pleiber	A-8-1		Date	11/06/2006	
प्रभाइड	PACE KOR FEDE	RAL OR STATE (	derice i	ISE TO THE REPORT OF THE PARTY	

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

those wants in the subject lease

CONDITIONS OF APPROVAL ATTACHE

DEC 2 1 2006

DaDEC 0 4 2006

NOTICE OF APPROVAL

Office

Title Petroleum Engineer

DIV. OF OIL, GAS & MINING



Approved by

Conditions of appro

certify that the applicant holds legal or equitable title to those which would entitle the applicant to conduct operations thereon.

#### DRILLING PLAN

#### **APPROVAL OF OPERATIONS**

#### Attachment for Permit to Drill

Name of Operator:

Dominion Exploration & Production

Address:

14000 Quail Springs Parkway, Suite 600

Oklahoma City, OK 73134

Well Location:

RBU 21-18F

SHL: 2379' FSL & 834' FWL Section 18-10S-20E BHL: 2450' FNL & 50' FWL Section 18-10S-20E

Uintah County, UT

1. GEOLOGIC SURFACE FORMATION

Uintah

#### 2. <u>ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS</u>

<u>Formation</u>	<u>Depth</u>
Wasatch Tongue	4,371
Uteland Limestone	4,740'
Wasatch	4,900'
Chapita Wells	5,810'
Uteland Buttes	7,060'
Mesaverde	7,950'

#### 3. ESTIMATED DEPTHS OF ANTICIPATED WATER. OIL, GAS OR MINERALS

<u>Formation</u>	<u>Depth</u>	<u>Type</u>
Wasatch Tongue	4,371'	Oil
Uteland Limestone	4,740'	Oil
Wasatch	4,900'	Gas
Chapita Wells	5,810'	Gas
Uteland Buttes	7,060	Gas
Mesaverde	7,950°	Gas

#### 4. PROPOSED CASING PROGRAM

All casing used to drill this well will be new casing.

Type	Size	<u>Weight</u>	<u>Grade</u>	Conn.	<u>Тор</u>	<u>Bottom</u>	<u>Hole</u>
Surface	13-3/8"	48.0 ppf	H-40	STC	0'	500'	17-1/2"
Intermediate	9-5/8"	36.0 ppf	J-55	STC	0,	3,550'	12-1/4"
Production	5-1/2"	17.0 ppf	MAV-80	LTC	0,	8,875	7-7/8"

#### 5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

Surface hole: No BOPE will be utilized.

Intermediate hole: To be drilled using a diverter stack with rotating head to divert flow from rig floor.

<u>Production hole</u>: Prior to drilling out the intermediate casing shoe, 3,000 psi or greater BOP equipment will be installed. The pipe rams will be operated at least once per day from surface to total depth. The blind rams will be tested once per day from surface to total depth if operations permit.

#### DRILLING PLAN

#### APPROVAL OF OPERATIONS

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. As denoted there will be two valves and one check valve on the kill line, two valves on the choke line, and two adjustable chokes on the manifold system. The BOP "stack" will consist of two BOP rams (1 pipe, 1 blind) and one annular type preventer, all rated to a minimum of 3,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling out surface casing shoe and anytime a new casing string is set. All test pressures will be maintained for fifteen (15) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items.

1.	Annular BOP	1,500 psi
2.	Ram type BOP	3,000 psi
3.	Kill line valves	3,000 psi
4.	Choke line valves and choke manifold valves	3,000 psi
5.	Chokes	3,000 psi
6.	Casing, casinghead & weld	1,500 psi
7.	Upper kelly cock and safety valve	3,000 psi
8.	Dart valve	3,000 psi

#### 6. MUD SYSTEMS

- An air or an air/mist system may be used to drill to drill the surface hole until water influx becomes too great.
- · KCL mud system will be used to drill well.
- The mud system will be monitored manually/visually.

<u>Depths</u>	Mud Weight (ppg)	Mud System
0' - 500'	8.4	Air foam mist, no pressure control
500' - 3,550'	8.6	Fresh water, rotating head and diverter
3,550' - 8,875'	8.6	Fresh water/2% KCL/KCL mud system

#### BLOOIE LINE

- An automatic igniter will not be installed on blooie line. The blooie will have a contant ignition source.
- A "target tee" connection will be installed on blooie line for 90° change of directions for abrasion resistance.
- "Target tee" connections will be a minimum of 50' from wellhead.
- The blooie line discharge will be a minimum of 80' from the wellhead.

#### 8. AUXILIARY EQUIPMENT TO BE USED

- a. Kelly cock. ·
- b. Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string.

#### 9. TESTING. LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

- A drillstem test in the Wasatch Tongue is possible.
- One electric line wire-log will be run from total depth to intermediate casing.
- The gamma ray will be left on to record from total depth to intermediate casing.
- Other log curves (resistivities, porosity, and caliper) will record from total depth to intermediate casing.
- A dipmeter, percussion cores, or rotary cores may be run over selected intervals.

#### 10. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

- Expected BHP 1,500-2,000 psi (lower than normal pressure gradient).
- No abnormal temperature or pressures are anticipated.
- The formations to be penetrated do not contain known H2S gas.

#### 11. WATER SUPPLY

- No water pipelines will be laid for this well.
- No water well will be drilled for this well.
- Drilling water for this will be hauled on the road(s) shown in Attachment No. 3.
- Water will be hauled from: Water Permit # 43-10447 Section 9, Township 8 South, Range 20 East

#### **DRILLING PLAN**

#### APPROVAL OF OPERATIONS

#### **CEMENT SYSTEMS**

- Surface Cement:
  - Drill 17-1/2" hole to 500' and cement 13-3/8" to surface with 450 sks class "C" cement with 2% CaCl<sub>2</sub> and 1/4 #/sk. Polyflake (volume includes 70% excess). Top out as necessary. Casing to be centralized with a total of 5 centralizers.
- Intermediate Casing Cement:
  - Drill 12-1/4" hole to 3,550'±, run and cement 9-5/8" to surface.
  - Pump 20 bbls lightly weighted water spacer followed by 5 bbls fresh water. Displace with any available water.
  - Casing to be run with: a) guide shoe b) insert float c) three (3) centralizers, one on each of first 3 joints d) stop ring for plug one joint off bottom e) bottom three joints thread locked f) pump job with bottom plug only. Casing to be centralized with a total of 15 centralizers.
  - Cement to surface not required due to surface casing set deeper than normal.

					<u>Hole</u>	<u>Cement</u>
<u>Type</u>	Sacks 5	<u>Interval</u>	<b>Density</b>	<u>Yield</u>	<u>Volume</u>	<u>Volume</u>
Lead	420	0'-3,050	10.5 ppg	4.14 CFS	993 CF	1,738 CF
Tail	254	3,050'-3,550'	15.6 ppg	1.2 CFS	174 CF	304 CF

Intermediate design volumes based on 75% excess of gauge hole.

Lead Mix: Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7.

Slurry yield: 4.14 cf/sack Slurry weight: 10.5 #/gal.

Water requirement: 26.07 gal/sack Compressives @ 110°F: 72 psi after 24 hours

Class "G" Cement, 1/4 lb/sk Cellophane Flakes + 2% bwoc Calcium Chloride + 46.5% fresh water. Tail Mix:

Slurry yield: 1.20 cf/sack Slurry weight: 15.6 #/gal.

Pump Time: 1 hr. 5 min. @ 110 °F.

Compressives @ 110 °F: 2,500 psi after 24 hours

#### c. Production Casing Cement:

- Drill 7-7/8" hole to 8,875'±, run and cement 5 1/2".
- Pump 20 bbl Mud Clean II unweighted spacer, followed by 20 Bbls fresh H20 spacer.
- Displace with 2% KCL.
- Production casing to be centralized with 30 centralizers.

					<u>Hole</u>	Cement
Type	<u>Sacks</u>	Interval	Density	<u>Yield</u>	<u>Volume</u>	<u>Volume</u>
Lead	90	4,100-4,900'	11.5 ppg	3.12 CFS	139 CF	277 CF
Tail	790	4,900-8,875	13.0 ppg	1.75 CFS	689 CF	1377 CF

Production design volumes based on 35% excess of gauge hole. Actual volumes will be calculated from caliper log to bring lead cement to 800' above top of Wasatch + 15% excess, and tail cement to top of Wasatch +15%.

Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7. Lead Mix:

> Slurry yield: 3.12 cf/sack Slurry weight: 11.60 #/gal.

17.71 gal/sack Water requirement:

Compressives @ 130°F: 157 psi after 24 hours

Tail Mix: Halliburton HLC blend (Prem Plus V/JB flyash). Blend includes Class "G" cement, KCl, EX-1, Halad 322,

& HR-5.

Slurry yield: 1.75 cf/sack Slurry weight: 13.00 #/gal.

Water requirement: 9.09 gal/sack

Compressives @ 165°F: 905 psi after 24 hours

#### 13. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

January 15, 2007 Starting Date:

Duration: 14 Days

Form 3160-3 (February 2005)

# RECEIVED

**UNITED STATES** 

DEPARTMENT OF THE II		2006	U013769-X			
BUREAU OF LAND MANA APPLICATION FOR PERMIT TO I			6. If Indian, Allotee o	r Tribe Name		
la. Type of work:  DRILL  REENTE	7 If Unit or CA Agreement, Name and No. River Bend Unit					
lb. Type of Well: Oil Well Gas Well Other	Single Zone Multip	ole Zone	8. Lease Name and W RBU 21-18F	ell No.		
2. Name of Operator  Dominion Exploration & Production, In	ec.		9. API Well No.			
3a. Address 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134	10. Field and Pool, or Ex Natural Buttes	ploratory				
4. Location of Well (Report location clearly and in accordance with any At surface 2,379' FSL & 834' FWL Lot 3 (NW/ At proposed prod. zone 2,450' FNL & 50' FWL, Lot 2 (SW/-	/4 SW/4),		11. Sec., T. R. M. or Bik Section 18, T10	and Survey or Area S, R20E, SLB&M		
14. Distance in miles and direction from nearest town or post office* 10.02 miles southwest of Ouray, Utah			12. County or Parish Uintah	13. State UT		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 834'	16. No. of acres in lease 791.86 acres	20 acı	ng Unit dedicated to this well			
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.  10'	to nearest well, drilling, completed,			//BIA Bond No. on file		
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5,080' GR	22 Approximate date work will sta 01/15/2007	rt*	23. Estimated duration 14 days			
	24. Attachments					
The following, completed in accordance with the requirements of Onshor  1. Well plat certified by a registered surveyor.  2. A Drilling Plan.  3. A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office).	4. Bond to cover t Item 20 above).  Lands, the 5. Operator certification	he operatio	is form:  ns unless covered by an elementary or services and or plans as			
25. Signature—Don Hamilton	Name (Printed/Typed)  Don Hamilton			08/31/2006		
Title Agent for Dominion						
Approved by (Signature)  Title   Signature   Signature	Name (Printed/Typed)  JELLY KENC	=KA		Date 12-7-2006		
Application approval does not warrant or certify that the applicant hold conduct operations thereon.  Conductions of approval, if any, are attached.  Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a conduction of approval to the section 1212 and the section	rime for any person knowingly and		A street A S S			

\*(Instructions on page 2)

NOTICE OF ELLANDED

CONFIDENTIAL

ORIGINAL



#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT VERNAL FIELD OFFICE

VERNAL FIELD OFFICE VERNAL, UT 84078

(435) 781-4400



#### **CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

Company: Dominion Expl. & Prod., Inc. Location: Lot 2, Sec 18, T10S, R20E

Well No: RBU 21-18F Lease No: UTU-013769
API No: 43-047-38554 Agreement: River Bend Unit

**170 South 500 East** 

Matt Baker Office: 435-781-4490 Petroleum Engineer: Cell: 435-828-4470 Petroleum Engineer: Michael Lee Office: 435-781-4432 Cell: 435-828-7875 Petroleum Engineer: Jim Ashlev Office: 435-781-4470 Cell: 435-838-7874 Supervisory Petroleum Technician: Jamie Sparger Office: 435-781-4502 Cell: 435-828-3913 **Environmental Scientist:** Paul Buhler Office: 435-781-4475 Cell: 435-828-4029

Environmental Scientist: Karl Wright Office: 435-781-4484
Natural Resource Specialist: Holly Villa Office: 435-781-4404
Natural Resource Specialist: Melissa Hawk Office: 435-781-4476
Natural Resource Specialist: Scott Ackerman Office: 435-781-4437
After Hours Contact Number: 435-781-4513 Fax: 435-781-4410

### A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit is approved for a one-year period. An additional year extension may be applied for by sundry notice prior to expiration.

#### **NOTIFICATION REQUIREMENTS**

Location Construction (Notify Karl Wright)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Karl Wright)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Matt Baker)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Jamie Sparger)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings.
BOP & Related Equipment Tests (Notify Jamie Sparger)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Matt Baker)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

COAs: Page 2 of 6 Well: RBU 21-18F

#### SURFACE USE PROGRAM CONDITIONS OF APPROVAL (COAs)

Surface Conditions of Approval or monitoring are listed in the Surface Use Plan of the APDs

- 1. **RBU 19-19F:** The access route will be rerouted around the East and South edge of the pad. No fill will be allowed to fall into the drainage. This reroute will be approximately 200 feet. The road will be returned to its present location upon reclaiming the pit.
- 2. Within 90 calendar days of the approval date for this Application for Permit to Drill (APD), the operator/lessee will submit to the Authorized Officer (AO), on Sundry Notice Form 3160-5, an Interim Surface Reclamation Plan for surface disturbance on well pads, access roads, and pipelines. At a minimum, this will include the Best Management Practice of the reshaping of the pad to the original contour to the extent possible; the re-spreading of the top soil up to the rig anchor points; and, reseeding the area using appropriate reclamation methods.
- 3. The interim seed mix for reclamation will be:

Hy-crest Crested Wheatgrass	4.	Agropyron cristatum	5.	4 lbs per acre
Western Wheatgrass	6.	Agropyron smithii	7.	4 lbs per acre
Needle and Threadgrass	8.	Stipa comata	9.	4 lbs per acre

- 4. If paleontologic materials are uncovered during construction, the operator shall immediately stop work that might further disturb such materials and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation will be necessary for the discovered paleontologic material.
- 5. Following well plugging and abandonment, the location, access roads, pipelines, and other facilities shall be reclaimed. All disturbed surfaces shall be reshaped to approximate the original contour; the top soil respread over the surface; and, the surface re-vegetated. The surface of approved staging areas where construction activities did not occur may require disking or ripping and reseeding.

COAs: Page 3 of 6 Well: RBU 21-18F

#### DOWNHOLE CONDITIONS OF APPROVAL

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

#### SITE SPECIFIC DOWNHOLE CONDITIONS OF APPROVAL

- 1. A Cement Bond Log (CBL) shall be run from the TD to the top of cement. A field copy of the CBL shall be submitted to the BLM Vernal Field Office for review.
- 2. Variance granted: Eighty foot long blooie line approved.

#### DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- 1. There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well. Any changes in operation must have prior approval from the BLM, Vernal Field Office Petroleum Engineers.
- 2. The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- 3. <u>Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.</u>
- 4. Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.

All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and <u>NOT</u> by the rig pumps. Test shall be reported in the driller's log.

BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.

Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.

No aggressive/fresh hard-banded drill pipe shall be used within casing.

5. The lessee/operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled and analyzed (a copy of the analyses to be submitted to the BLM Field Office in Vernal, Utah).

COAs: Page 4 of 6 Well: RBU 21-18F

6. All oil and gas shows shall be adequately tested for commercial possibilities, reported, and protected.

- 7. The lessee/operator must report encounters of all non oil & gas mineral resources (such as gilsonite, tar sands, oil shale, etc.) to Peter Sokolosky or another geologist of the Vernal Field Office in writing within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- 8. No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM, Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM, Vernal Field Office shall be obtained and notification given before resumption of operations.
- 9. Chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.

Any change in the program shall be approved by the BLM, Vernal Field Office. "Sundry Notices and Reports on Wells" (Form BLM 3160-5) shall be filed for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Emergency approval may be obtained orally, but such approval does not waive the written report requirement. Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan pursuant to Onshore Oil & Gas Order No. 1 of 43 CFR 3164.1 and prior approval by the BLM, Vernal Field Office.

In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.

10. Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

COAs: Page 5 of 6 Well: RBU 21-18F

A cement bond log (CBL) will be run from the production casing shoe to the surface casing shoe and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Please submit an electronic copy of all other logs run on this well in LAS format to UT\_VN\_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.

11. All off-lease storage, off-lease measurement, or commingling on-lease or off-lease shall have prior written approval from the BLM, Vernal Field Office.

All measurement points shall be identified as point of sales or allocation for royalty determination prior to the installation of facilities.

- 12. Oil and gas meters shall be calibrated in place prior to any deliveries. The Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM, Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement.
- 13. A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM, Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- 14. This APD is approved subject to the requirement that, should the well be successfully completed for production, the BLM, Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - a. Operator name, address, and telephone number.
  - b. Well name and number.

ζ

- c. Well location (1/41/4, Sec., Twn, Rng, and P.M.).
- d. Date well was placed in a producing status (date of first production for which royalty will be paid).
- e. The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
- f. The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.

COAs: Page 6 of 6 Well: RBU 21-18F

g. Unit agreement and / or participating area name and number, if applicable.

- h. Communitization agreement number, if applicable.
- 15. Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from Field Office Petroleum Engineers.
- 16. All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production
- 17. Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- 18. Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

# Division of Oil, Gas and Mining OPERATOR CHANGE WORKSHEET

	R	OUTING
	1.	DJJ
1	2	CDW

<b>X - Change o</b>	f Operator (	(Well Sold)
---------------------	--------------	-------------

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:			1		7/1/2007				
FROM: (Old Operator):				TO: (New O	nerator).				
N1095-Dominion Exploration & Production, Inc									
	14000 Quail Springs Parkway, Suite 600			N2615-XTO Energy Inc 810 Houston St					
Oklahoma City, OK 73134				4		(102			
Oktanoma City, Ok. 73134				roit w	orth, TX 76	5102			
Phone: 1 (405) 749-1300				Phone: 1 (817)	870-2800				
CA No.				Unit:		RIVER E	END		
WELL NAME	SEC	TWN	RNG	API NO	ENTITY	LEASE TYPE	WELL	WELL	
					NO		TYPE	STATUS	
SEE ATTACHED LIST									
OPERATOR CHANGES DOCUMENT	A TIT	ONI							
Enter date after each listed item is completed	AII	UN							
1. (R649-8-10) Sundry or legal documentation wa	g #00	airrad G	om tha	EODMED		9/6/2007			
				_		8/6/2007			
2. (R649-8-10) Sundry or legal documentation wa				_		8/6/2007			
3. The new company was checked on the <b>Departs</b>		of Con	amerce		-			8/6/2007	
4a. Is the new operator registered in the State of U				Business Numb	er:	5655506-0143			
4b. If NO, the operator was contacted contacted of	n:								
5a. (R649-9-2)Waste Management Plan has been re	ceive	d on:		IN PLACE					
5b. Inspections of LA PA state/fee well sites compl	lete o	n:		n/a	-				
5c. Reports current for Production/Disposition & S	undri	es on:		ok	-				
6. Federal and Indian Lease Wells: The BL	M an	d or the	e BIA h	as approved the	- e merger, na	me change			
or operator change for all wells listed on Federa					BLM	<del>-</del> ·	BIA		
7. Federal and Indian Units:						•		•	
The BLM or BIA has approved the successor	ofu	nit oner	ator for	wells listed on	•				
8. Federal and Indian Communization Ag					•	<del></del>			
The BLM or BIA has approved the operator is						•			
9. Underground Injection Control ("UIC"					oved UIC F	orm 5, Transfer	of Autho	rity to	
Inject, for the enhanced/secondary recovery un	•					•	OI AUUM	nity to	
DATA ENTRY:	to pro	ject 101	uic wa	itei disposai wei	n(s) nsied o				
1. Changes entered in the Oil and Gas Database	om.			0/27/2007					
<ol> <li>Changes entered in the On and Gas Database</li> <li>Changes have been entered on the Monthly Or</li> </ol>		or Cha	ngo Sn	9/27/2007	-	9/27/2007			
3. Bond information entered in RBDMS on:	ici ati	от Спа	nge sp	9/27/2007		912112001			
4. Fee/State wells attached to bond in RBDMS on	•			9/27/2007	-				
5. Injection Projects to new operator in RBDMS of				9/27/2007	•				
6. Receipt of Acceptance of Drilling Procedures f		D/New	on:		9/27/2007				
BOND VERIFICATION:						•			
1. Federal well(s) covered by Bond Number:				UTB000138					
2. Indian well(s) covered by Bond Number:			•	n/a	•				
3a. (R649-3-1) The NEW operator of any state/fe	e wel	l(s) list	ed cove	ered by Bond Nu	umber	104312762			
3b. The <b>FORMER</b> operator has requested a releas	e of l	iability	from th	eir bond on:	1/23/2008				
The Division sent response by letter on:		•				•			
LEASE INTEREST OWNER NOTIFIC	ATI	ON:							
4. (R649-2-10) The NEW operator of the fee wells			ntacted	and informed b	y a letter fro	om the Division			
of their responsibility to notify all interest owner					-				
COMMENTS:									

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL, GAS AND MINING	5. LEASE DESIGNATION AND SERIAL NUMBER:
SUNDRY NOTICES AND REPORTS ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL GAS WELL V OTHER	8. WELL NAME and NUMBER:
	SEE ATTACHED
2. NAME OF OPERATOR:	9. API NUMBER:
XTO Energy Inc. N34/5  3. ADDRESS OF OPERATOR: 810 Houston Street PHONE NUMBER:	SEE ATTACHED
OTO FIGURE	10. FIELD AND POOL, OR WILDCAT:
CITY FOR WORTH STATE TX ZIP 76102 (817) 870-2800 4. LOCATION OF WELL	Natural Buttes
FOOTAGES AT SURFACE: SEE ATTACHED	соинту: Uintah
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION TYPE OF ACTION	
✓ NOTICE OF INTENT ACIDIZE DEEPEN	REPERFORATE CURRENT FORMATION
(Submit in Duplicate) ALTER CASING FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will start: CASING REPAIR NEW CONSTRUCTION	TEMPORARILY ABANDON
CHANGE TO PREVIOUS PLANS	TUBING REPAIR
CHANGE TUBING PLUG AND ABANDON	VENT OR FLARE
SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK	
(Submit Original Form Only)	WATER DISPOSAL
Date of work completion:	WATER SHUT-OFF
COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE	OTHER:
CONVERT WELL TYPE RECOMPLETE - DIFFERENT FORMATION	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volume	
Effective July 1, 2007, XTO Energy Inc. has purchased the wells listed on the attachment	from:
Dominion Exploration & Production, Inc. 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134	
James D. Abercrombie Sr. Vice President, General Manager - Western Business Unit  Please be advised that XTO Energy Inc. is considered to be the operator on the attached under the terms and conditions of the lease for the operations conducted upon the lease is provided by Nationwide BLM Bond #104312750 and Department of Natural Resources	ands. Bond coverage
NAME (PLEASE PRINT) Edwin S. Ryan, Jr.  SIGNATURE  DATE 7/31/2007	t - Land Administration
This space for State use only)	RECEIVED
APPROVED 7 13/10/	
APPROVED 9131107  Eq. legg Risall	AUG 0 6 2007

(5/2000)

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

DIV. OF OIL, GAS & MINING

# STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

#### Request to Transfer Application or Permit to Drill

Well name:	SEE ATTACH	HED LIST		·	
API number:					
Location:	Qtr-Qtr:	Section:	Township: Range	<del> </del>	
Company that filed original application:	DOMINION E				
Date original permit was issued:					
Company that permit was issued to:	DOMINION	E&P			
Check		·	····		
one		ired Action:			
・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・ ・					
Transfer pending (unapproved) App					
The undersigned as owner with legal submitted in the pending Application f owner of the application accepts and	or Permit to Dri	I, remains valid ar	nd does not require revision. The	e new	
√ Transfer approved Application for I	Permit to Drill t	o new operator			
The undersigned as owner with legal information as submitted in the previo	rights to drill on	the property as po	ermitted, hereby verifies that the	ire	
revision.	usiy appioved a	application to drill,	remains valid and does not requ		
revision.					
revision.  Following is a checklist of some items re	ated to the ap			Yes	-
revision.  Following is a checklist of some items re	ated to the ap				-
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement beer	ated to the ap changed?	plication, which s	should be verified.		-
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement beer  Have any wells been drilled in the vicinity of requirements for this location?	ated to the ap changed? updated?	plication, which s	should be verified.  fect the spacing or siting		v
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement beer  Have any wells been drilled in the vicinity of requirements for this location?  Have there been any unit or other agreement	ated to the ap changed? updated?	plication, which s	should be verified.  fect the spacing or siting		•
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement been have any wells been drilled in the vicinity of requirements for this location?  Have there been any unit or other agreemer proposed well?  Have there been any changes to the access	changed? updated? the proposed w	plication, which seem of the s	should be verified.  fect the spacing or siting the permitting or operation of this		<b>*</b>
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement beer  Have any wells been drilled in the vicinity of requirements for this location?  Have there been any unit or other agreemer proposed well?  Have there been any changes to the access proposed location?	changed? updated? the proposed w ts put in place	plication, which seem of the s	should be verified.  fect the spacing or siting the permitting or operation of this		N
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement been have any wells been drilled in the vicinity of requirements for this location?  Have there been any unit or other agreement proposed well?  Have there been any changes to the access proposed location?  Has the approved source of water for drilling have there been any physical changes to the	changed? updated? the proposed wats put in place route including changed? e surface locati	plication, which sell which would at that could affect the ownership or righ	should be verified.  Flect the spacing or siting the permitting or operation of this tof-way, which could affect the		v v
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement beer  Have any wells been drilled in the vicinity of requirements for this location?  Have there been any unit or other agreemer proposed well?  Have there been any changes to the access proposed location?  Has the approved source of water for drilling have there been any physical changes to the plans from what was discussed at the onsite	changed? updated? the proposed w ts put in place route including changed? e surface locati evaluation?	plication, which seem of the could affect the country or right on or access route	should be verified.  fect the spacing or siting te permitting or operation of this t-of-way, which could affect the		,
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement beer Have any wells been drilled in the vicinity of requirements for this location?  Have there been any unit or other agreemer proposed well?  Have there been any changes to the access proposed location?  Has the approved source of water for drilling have there been any physical changes to the plans from what was discussed at the onsite is bonding still in place, which covers this proposed begins or necessary changes to either should be filed on a Sundry Notice, Form 9, necessary supporting information as require	changed? updated? the proposed w tts put in place route including changed? e surface locati evaluation? oposed well? E a pending or apor amended Ap	plication, which so rell which would at that could affect the ownership or right on or access route and No. 1043127	should be verified.  fect the spacing or siting the permitting or operation of this theorem which could affect the the which will require a change in the permit to Drill that is being the permit to Drill, Form 3, as appropriate	Yes	v v
Following is a checklist of some items re  If located on private land, has the ownership  If so, has the surface agreement beer Have any wells been drilled in the vicinity of requirements for this location?  Have there been any unit or other agreemer proposed well?  Have there been any changes to the access proposed location?  Has the approved source of water for drilling have there been any physical changes to the plans from what was discussed at the onsite is bonding still in place, which covers this proposed or necessary changes to either should be filed on a Sundry Notice, Form 9,	changed? updated? the proposed w tts put in place route including changed? e surface locati evaluation? oposed well? E a pending or apor amended Ap	plication, which so rell which would at that could affect the ownership or right on or access route and No. 1043127	should be verified.  fect the spacing or siting the permitting or operation of this theorem which could affect the the which will require a change in for Permit to Drill that is being the permit to Drill, Form 3, as appropriate	Yes	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

AUG 3 0 2007

#### N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

#### RIVER BEND UNIT

api	well_name	qtr_qtr	sec	twp	mg	lease_num	entity	Lease	well	stat
4304736202	RBU 2-20E	NWNE	20	100S	190E	U-03505		Federal	GW	APD
4304736203	RBU 15-20E	SWSE	20	100S	190E	U-03505		Federal	GW	APD
4304736204	RBU 10-20E	NWSE	20	100S	190E	U-03505		Federal	GW	APD
4304736205	RBU 14-21E	SESW	21	100S	190E	U-013766		Federal	GW	APD
4304736295	RBU 10-21E	NWSE	21	100S	190E	U-013766		Federal	GW	APD
4304736426	RBU 7-9E	NWSE	09	100S	190E	U-03505		Federal	GW	APD
4304736430	RBU 16-20E	SESE	20	100S	190E	U-03505		Federal	GW	APD
4304736431	RBU 13-21E	SESE	20	100S	190E	U-013766		Federal	GW	APD
4304736606	RBU 14-11F	SESW	11	100S	200E	U-7206		Federal	GW	APD
4304737032	RBU 1-4E	NENE	04	100S	190E	U-013792		Federal	GW	APD
4304737423	RBU 2-21F	SWSE	16	100S	200E	U-013793-A		Federal	OW	APD
4304737569	RBU 14-15F	SESW	15	100S	200E	U-7206		Federal	OW	APD
4304737648	RBU 6-4E	SWNE	04	100S	190E	U-013792		Federal	GW	APD
4304737649	RBU 12-17E	NWSW	17	100S	190E	U-03505		Federal	GW	APD
4304737650	RBU 13-17E	SWSW	17	100S	190E	U-03505		Federal	GW	APD
4304737651	RBU 6-23E	SENW	23	100S	190E	U-013766		Federal	GW	APD
4304737652	RBU 7-16F	SWNE	16	100S	200E	U-7206		Federal	GW	APD
4304737748	RBU 14-16F	SWSE	16	100S	200E	U-7206		Federal	GW	APD
4304738341	RBU 15-21E	SWSE	21	100S	190E	U 013766		Federal	GW	APD
4304738544	RBU 18-24E	SWSE	13	100S	190E	U 013794		Federal	GW	APD
4304738545	RBU 19-24E	SWSE	13	100S	190E	U 013794		Federal	GW	APD
4304738546	RBU 25-13E	NWSE	13	100S	190E	U-013765		Federal	GW	APD
4304738547	RBU 31-13E	NWSE	13	100S	190E	U-013765		Federal	GW	APD
4304738549	RBU 17-24E	NWNW	19	100S	200E	U-013794		Federal	GW	APD
4304738550	RBU 18-19F	NENW	19	100S	200E	U 013769-A		Federal	GW	APD
4304738551	RBU 19-19F	NWNW	19	100S	200E	U 013769-A		Federal	GW	APD
4304738552	RBU 20-19F	NWNW	19	100S	200E	U 013769-A		Federal	GW	APD
4304738553	RBU 23-19F	NENW	19	100S	200E	U013769-A		Federal	GW	APD
4304738554	RBU 21-18F	NWSW	18	100S	200E	U013769-A		Federal	GW	APD
4304738582	RBU 17-10E	NWNE	10	100S	190E	U-013792		Federal	GW	APD
4304738583	RBU 18-10E	NWNE	10	100S	190E	U-013792		Federal	GW	APD
4304738584	RBU 27-10E	SWSE	10	100S	190E	U-013792		Federal	GW	APD
4304738585	RBU 26-10E	NESE	10	100S	190E	U-013792		Federal	GW	APD
4304738586	RBU 25-10E	NESE	10			U-013792		Federal	GW	APD
4304738587	RBU 23-10E	NESE	10	100S	190E	U-013792		Federal	GW	APD
4304738588	RBU 22-10E	SWNW	10	100S	190E	U-035316		Federal	GW	APD
4304738589	RBU 21-14E	NWSW	14	100S	190E	U-013792		Federal	GW	APD
4304738590	RBU 27-14E	NWSW	14			U-013792		Federal	GW	APD
4304738591	RBU 25-14E	NESE	14			U-013792		Federal		<del></del>
4304738592	RBU 24-14E	NENE	14			U-013792		Federal		
4304738593	RBU 23-14E	SENW	14			U-013792		Federal		
4304738594	RBU 30-10E	NENW	15			U-013792		Federal		
4304738597	RBU 18-15E	NENW	15			U-013766		Federal		
4304738598	RBU 20-14E	SENE	15			U-013792		Federal		+



### United States Department of the Interior

# BUREAU OF LAND MANAGEMENT Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155



1 66 4

IN REPLY REFER TO 3180 UT-922

Dominion Exploration & Production, Inc. Attn: James D. Abercrombie 14000 Quail Springs Parkway, #600 Oklahoma City, OK 73134-2600

August 10, 2007

Re:

River Bend Unit Uintah County, Utah

#### Gentlemen:

On August 8, 2007, we received an indenture dated June 30, 2007, whereby Dominion Exploration & Production, Inc. resigned as Unit Operator and XTO Energy Inc. was designated as Successor Unit Operator for the River Bend Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective August 15, 2007. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the River Bend Unit Agreement.

Your statewide oil and gas bond No. UTB000138 will be used to cover all operations within the River Bend Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Greg J. Noble

Greg J. Noble Acting Chief, Branch of Fluid Minerals

**Enclosure** 

RECEIVED
AUG 1 6 2007
DIV. OF OIL, GAS & MINING

### RECEIVED SEP 1 U 2007

STATE OF UTAH

CEO. CEO. CAC O MINIMO

	М	

1	DEPARTMENT OF NATURAL RESOUI DIVISION OF OIL, GAS AND MI	RCESV OF OIL, GAS & MINING INING	5. LEASE DESIGNATION AND SERIAL NUMBER: U-013769-A
SUNDRY	NOTICES AND REPORTS	S ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
Do not use this form for proposals to drill no	ew wells, significantly deepen existing wells below cu terals. Use APPLICATION FOR PERMIT TO DRILL	urrent bottom-hole depth, reenter plugged wells, or to form for such proposals.	7. UNIT OF CA AGREEMENT NAME: River Bend Unit
1. TYPE OF WELL OIL WELL	GAS WELL OTHER_		8. WELL NAME and NUMBER: RBU 21-18F
2. NAME OF OPERATOR:			9. API NUMBER:
XTO Energy		PHONE NUMBER:	4304738554  10. FIELD AND POOL, OR WILDCAT:
3. ADDRESS OF OPERATOR: P.O. Box 1360	Roosevelt STATE UT ZIE	L'ON CONTRACTOR DE LA C	Natural Buttes
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2,379'	FSL & 834' FWL		соинту: Uintah
QTR/QTR, SECTION, TOWNSHIP, RAN		20E S	STATE: UTAH
11. CHECK APP	ROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	REPERFORATE CURRENT FORMATION
NOTICE OF INTENT	ACIDIZE	DEEPEN FRACTURE TREAT	SIDETRACK TO REPAIR WELL
(Submit in Duplicate)  Approximate date work will start:	ALTER CASING  CASING REPAIR	NEW CONSTRUCTION	TEMPORARILY ABANDON
Approximate date work will start.	CHANGE TO PREVIOUS PLANS	OPERATOR CHANGE	TUBING REPAIR
	CHANGE TUBING	PLUG AND ABANDON	VENT OR FLARE
SUBSEQUENT REPORT	CHANGE WELL NAME	PLUG BACK	WATER DISPOSAL .
(Submit Original Form Only)	CHANGE WELL STATUS	PRODUCTION (START/RESUME)	WATER SHUT-OFF
Date of work completion:	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE	✓ отнек: Permit Extension
	CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION	l .
XTO Energy. hereby requ	that has been requested.	e state permit for the referenced v	vell.
	Utah Divisior Oil, Gas and M	Mining	
	Date: 10-02		COPY SENT TO OPERATOR Porte: 10-3-01 Initials: RM
NAME (PLEASE PRINT) Marnie G	riffin	TITLE Agent for XTO	Energy
SIGNATURE	<u>M/</u>	DATE 9/7/2007	
(This space for State use only)	<del></del>		

### RECEIVED SEP 1 U 2007

### D:V. OF OIL, GAS & MINING

#### Application for Permit to Drill Request for Permit Extension Validation

Validation
(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738554 Well Name: RBU 21-18F Location: 18-10S-20E 2,379' FSL & 834' FWI Company Permit Issued to: XTO Energy Date Original Permit Issued: 9/25/2006	• •
The undersigned as owner with legal rights above, hereby verifies that the information a approved application to drill, remains valid a	is submitted in the previously
Following is a checklist of some items relate verified.	ed to the application, which should be
If located on private land, has the ownership agreement been updated? Yes ☐ No ☑	o changed, if so, has the surface
Have any wells been drilled in the vicinity of the spacing or siting requirements for this lo	f the proposed well which would affect ocation? Yes⊟No☑
Has there been any unit or other agreemen permitting or operation of this proposed we	ts put in place that could affect the ∥? Yes⊟No☑
Have there been any changes to the acces of-way, which could affect the proposed loc	s route including ownership, or right- ation? Yes⊟ No ☑
Has the approved source of water for drilling	g changed? Yes□No☑
Have there been any physical changes to t which will require a change in plans from w evaluation? Yes□No☑	he surface location or access route hat was discussed at the onsite
Is bonding still in place, which covers this p	roposed well? Yes ☑ No □
$\mathcal{M}$	9/7/2007 Date
Signature	Date
Title: Agent	
Representing: XTO Energy	

Form 3160-5 (February 2005)

#### UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT**

#### SUNDRY NOTICES AND REPORTS ON WELLS

Change Plans

Convert to Injection

FORM APPROVED
OM B No. 1004-0137
Expires: March 31, 2007

5.	Lease Serial No.
	U 013769-A

6.	If Indian,	or Tribe	Name

abandoned w	N/A				
SUBMIT IN TR	7. If Unit or CA/Agreement, Name and/or No.				
Type of Well Oil Well      Name of Operator XTO Energy	Gas Well Other		River Bend Unit  8. Well Name and No. RBU 21-18F  9. API Well No.		
3a Address PO Box 1360; 978 North Cres	cent, Roosevelt, UT 84066	3b. Phone No. (include area code) 435-722-4521	4304738554  10. Field and Pool, or Exploratory Area		
4. Location of Well (Footage, Sec.,	T., R., M., or Survey Description)		Natural Buttes		
2,379' FSL & 834' FWL Lot 3	3 (NW/4 SW/4), Section 18, T1	0S, R20E, SLB&M	11. County or Parish, State		
			Uintah County, Utah		
12. CHECK A	PPROPRIATE BOX(ES) TO	INDICATE NATURE OF NOTICE	, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION		TYPE OF ACTION	<b>V</b>		
Notice of Intent	Acidize Alter Casing	Fracture Treat Reclamati			
Subsequent Report	Casing Repair	New Construction Recomple	te Other Permit Extension		

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Plug and Abandon

Plug Back

Temporarily Abandon

Water Disposal

XTO Energy hereby requests a one year extension of the federal permit for the referenced well that expires on 12-7-07.

This is the first extension that has been requested. The federal permit was formerly in the name of Dominion Exploration & Production. Inc.

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed)	1
Don Hamilton	Title Agent for XTO Energy, Inc.
Signature Don Hamilton	Date 10-10- 2007
THIS SPACE FOR FEDERAL	OR STATE OFFICE USE
Approved by	Petroleum Engineer OCT 22 2007
Conditions of approval, if any, are attached. Approval of this notice does not warracertify that the applicant holds legal or equitable title to those rights in the subject lewhich would entitle the applicant to conduct operations thereon.	nt or
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any States any false, fictitious or fraudulent statements or representations as to any matter	person knowingly and willfully to make to any department or agency of the United r within its jurisdiction.

(Instructions on page 2)

Final Abandonment Notice

RECEIVED

NOV 0 7 2007 CONDITIONS OF APPROVAL ATTACHED



### **CONDITIONS OF APPROVAL**

### XTO Energy, Inc.

# **Notice of Intent APD Extension**

Lease:

UTU-013769-A

Well:

RBU 21-18F

Location:

NWSW Sec 18-T10S-R20E

An extension for the referenced APD is granted with the following conditions:

- 1. The extension and APD shall expire on 12/7/08.
- 2. No other extension shall be granted.

If you have any other questions concerning this matter, please contact Ryan Angus of this office at (435) 781-4430

### **DIVISION OF OIL, GAS AND MINING**

#### **SPUDDING INFORMATION**

Name of Co	mpany:		XTO E	NER(	GY INC			
Well Name:			RBU 21	<u>l-18F</u>				
Api No:	43-047-3	88554			Lease Typ	e: <u>FEDI</u>	ERAL	
Section_18_	_Township_	10S	_Range_	20E	County	UINTA	МН	
Drilling Cor	ntractor	P	ETE MA	RTI	N DRILLING	RIG #	5	
SPUDDE	D:							
	Date	0	7/27/08	·	_			
	Time		·		<del></del>			
	How	<u>D</u>	RY					
Drilling w	ill Comme	ence:_						
Reported by	-		MIKE	LIND	SEY			
Telephone #			(435) 8	<b>328-5</b> 4	66			· ·
Date	07/28/08		Signed	ii	CHD			

#### STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM					
Operator:	XTO ENERGY INC.		Operator Account Number: N 2615		
Address:	382 CR 3100		<del></del>		
	city AZTEC				
	state NM	zip 87410	Phone Number: (505) 333-3100		

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304738554	RBU 21-18F		NWSW	18	108	20E	UINTAH
Action Code	Current Entity Number	New Entity Number	1	pud Da	te		y Assignment ective Date
Α	99999	7050		7/26/200	8	7/3	31/08
Comments:	, , , , , , , , , , , , , , , , , , , ,					1 /	
MURB =	WSMVN	BAL = SWA	$1 \omega$				

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	i S	Spud Da	te		y Assignment ective Date
omments:							

API Number	Well N	lame	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	S	Spud Da	te		ity Assignmen iffective Date
				, <del>-</del>			

WANETT MCCAULEY

7/28/2008

Name (Please Print)

Signature

Title

FILE CLERK

#### **ACTION CODES:**

(5/2000)

- A Establish new entity for new well (single well only)
- B Add new well to existing entity (group or unit well)
- C Re-assign well from one existing entity to another existing entity
- Re-assign well from one existing entity to a new entity
- E Other (Explain in 'comments' section)

**RECEIVED** 

JUL 2 8 2008

DIV. OF OIL, GAS & MINING



# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

### SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPRO	VED
OMB NO. 1004	I-0131
Expires July 31	2010

5. Lease Serial No.

<u>U-</u>	013	376	9-A	

6. If Indian, Allottee or Tribe Name

		N/A
SUBMIT IN TRIPLICATE - Other instructio	ns on page 2	7. If Unit or CA/Agreement, Name and/or No RIVERBEND UNIT
1. Type of Well Oil Well X Gas Well Other  2. Name of Operator		8. Well Name and No. RBU 21-18F
XTO Energy Inc.  3a. Address	2h Dhomo No (include manufa)	9. API Well No.
382 CR 3100 Aztec, NM 87410	3b. Phone No. (include area code)	43-047-38554
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)	505-333-3100	10. Field and Pool, or Exploratory Area  NATURAL BUTTES
SHL: 2379' FSL & 834' FWL NWSW SEC 18-T10S-R20E	SLB&M	NATURAL BUILES
BHL: 2450' FNL & 50' FWL SWNW SEC 18-T10S-R20E	<del></del>	11. County or Parish, State UINTAH UT
12. CHECK APPROPRIATE BOX(ES) TO INC	DICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent  Acidize  Alter Casing  Casing Repair	Deepen Production  Fracture Treat Reclamation  New Construction Recomplet	
Change Plans		iy Abandon
Final Abandonment Notice		
Convert to Injection	on Plug Back Water Dis	oosal
following completion of the involved operations. If the operation results in testing has been completed. Final Abandonment Notices shall be filed on determined that the final site is ready for final inspection.)  XTO Energy Inc. spudded 20" conductor hole @ 12: cemented conductor csg w/5 yds Redimix cement.  Drilling ahead	nly after all requirements, including reclamation	on, have been completed, and the operator has
		RECEIVED
		AUG - 1 2008
14. I hereby certify that the foregoing is true and correct	l	
Name (PrintedTyped) WANEIT MCCAULEY	Title FILE CLERK	DIV. OF OIL, GAS & MINING
Signature Want Macauly	Date 7/29/2008	
THIS SPACE FOR FEE	DERAL OR STATE OFFICE USE	
Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or cert the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	tify that Office	
Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any per fictitious or fraudulent statements or representations as to any matter within its jurisdiction	rson knowingly and willfully to make to any departm	ent or agency of the United States any false,



#### **UNITED STATES** DEPARTMENT OF THE INTERIOR

# BUREAU OF LAND MANAGEMENT

rokwi Ai	PROVED
OMB NO.	1004-0137
Expires Jul	ly 31, 2010

5. Lease Serial No.

 ~-	2000	-	

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill or to re-enter an

6. If Indian, Allottee or Tribe Name

abandoned well. Use Form	N/A	N/A			
SUBMIT IN TRIPLICAT	7. If Unit or CA/Agreement, Name and/or No RIVERBEND UNIT  8. Well Name and No. RBU 21-18F				
1. Type of Well Oil Well X Gas Well Other  2. Name of Operator					
XTO Energy Inc.  3a. Address  382 CR 3100 Aztec, NM 87410		3b. Phone No. ( <i>include ar</i> 505-3	rea code) 33-3100	9. API Well N 43-047-38 10. Field and	
BHL: 2450' FNL & 50' FWL SWNW S	EC 18-T10S-R20E EC 18-T10S-R20E	SLB&M		UINTAH	r Parish, State
12. CHECK APPROPRIATE TYPE OF SUBMISSION	E BOX(ES) TO INI		PE OF ACTION	ORT, OR OTH	ER DATA
Notice of Intent  X Subsequent Report  Final Abandonment Notice	Acidize Alter Casing Casing Repair Change Plans Convert to Injection	Deepen Fracture Treat New Construction Plug and Abandon Plug Back	Reclamati	ite ily Abandon	Water Shut-Off Well Integrity  X Other JULY '08  MONTHLY REPORT
13. Describe Proposed or Completed Operation (clearly If the proposal is to deepen directionally or recomp					

Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Attached is XTO Energy's monthly report for the period of 7/01/2008 thru 7/31/2008.

RECEIVED AUG 1 1 2008

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed)  WANETE MCCAULEY	Title FILE CLERK					
Signature Want McCauley	Date 8/04/2008					
THIS SPACE FOR FEDERAL OR STATE OFFICE USE						
Approved by	Title	Date				
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office Office					

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

#### Farmington Well Workover Report

RIVERBE	ND UNIT	Well # 021-18F	
Objective:	Drill & Complete		
First Report:	06/30/2008		
AFE:	717118		
7/1/08	First rpt for AFE # 717118 to D&C. MIR Susp rpts pending further activity.	U Larose Const. STD Cons	et of loc pad on 6/17/08. RDMO Larose Const 6/19/08.

#### EXECUTIVE SUMMARY REPORT

7/1/2008 - 7/31/2008 Report run on 8/4/2008 at 11:37 AM

RBU 21-18F - Natural Buttes, 18, 10S, 20E, Uintah, Utah, , Roosevelt,

AFE: 717118

Objective: Drill & Complete a Natural Buttes gas well Rig Information: Pete Martin Drilling, 3,

7/27/2008

MOVE IN PETE MARTIN AND DRILL 20" CONDUCTOR TO 40', RAN 40' OF 14" CONDUCTOR PIPE, CALLED IN SPUD TO STATE OF UTAH CAROL DANIELS AND JAMMIE SPARGER WITH BLM ON 7-25-08 ,CMT CONDUCTOR WITH 5 YARDS REDIMIX CMT.

CMT TO SURF, DRILL AND SET RAT & MOUSE HOLE

MOVE IN PETE MARTIN AND DRILL 20" CONDUCTOR TO 40', RAN 40' OF 14" CONDUCTOR PIPE, CALLED IN SPUD TO STATE OF UTAH CAROL DANIELS AND JAMMIE SPARGER WITH BLM ON 7-25-08, CMT CONDUCTOR WITH 5 YARDS REDIMIX CMT.

CMT TO SURF, DRILL AND SET RAT & MOUSE HOLE

Form 3160-5 (August 2007)

#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

SHINDRY	NOTICES	AND	PEDODIC	ON	\A/⊏I	1 0

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly

fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

FORM APPRO	VED
OMB NO. 1004	-0137
Evniree July 31	2010

~	• •	^-	_		Ο.	•	v	•	0.	-
E	X	pi	ir	es	Ju	ly	31	,	20	1
 _	$\bar{\cdot}$		_	Ţ						_

п	٥.	Doube	001	ш	٠,
1					
ı	TT	0127	202		

י	<u>- 013703</u>	Λ.		
	If Indian	4.44		
	It Indian	Allottaa	or Iribo	None

partment or agency of the United States any false,


Do not use this form for abandoned well. Use For	6. If Indian, Allottee or	6. If Indian, Allottee or Tribe Name		
			N/A	
SUBMIT IN TRIPLICA	<b>TE -</b> Other instruction	ons on page 2	7. If Unit or CA/Agreer RIVERBEND UNIT	nent, Name and/or No.
1. Type of Well Oil Well X Gas Well Other			8. Well Name and No.	
2. Name of Operator			RBU 21-18F	
XTO Energy Inc.				
3a. Address		3b. Phone No. (include area code)	9. API Well No.	
382 CR 3100 Aztec, NM 87410		505-333-310	0 43-047-38554 10. Field and Pool, or I	Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey	Description)		NATURAL BUTTES	
	SEC 18-T10S-R20E		11.0 0	
BHL: 2450' FNL & 50' FWL SWNW S	SEC 18-T10S-R20E		11. County or Parish, S	
12. CHECK APPROPRIATI	E BOX(ES) TO INI	DICATE NATURE OF NOTICE	REPORT, OR OTHER DAT	A UT
TYPE OF SUBMISSION		TYPE OF A	CTION	
X Notice of Intent	Acidize	Deepen P	roduction (Start/Resume) Wa	ater Shut-Off
_	Alter Casing	Fracture Treat R	eclamation We	ll Integrity
Subsequent Report	Casing Repair	New Construction R	一	her
<u></u>	X Change Plans		emporarily Abandon	
Final Abandonment Notice	Convert to Injection		Vater Disposal	
	Convert to injection	Ting Back		
testing has been completed. Final Abandonment I determined that the final site is ready for final inspective to the state of the state	ction.) approval from Ma			•
COPY SENT TO OPERATOR		٠ ١	ECEIVED AUG 0 4 2008 OF OIL, GAS & MINING	
Date: 8 : 14 · 2008 Initials: 165				
14. I hereby certify that the foregoing is true and correct Name (Printed/Typed)  LORRI D. BINCHAM	0	Title REGULATORY C	OMPLIANCE TECH	
Signature	(am)	Date 7/31/08		
Тіўіз		ERAL OR STATE OFFICE US	- E	Of This
Approved by		Title 1201 Law Gott	Date.	sary
Conditions of approval, if any, are attached. Approval of this not the applicant holds legal or equitable title to those rights in the sub			1	



To cc

bcc

Subject Fw: RBU 21-18F



To Nancy Gibson/FAR/CTOC

CC

Subject Fw: RBU 21-18F

Here is the paperwork with the changes that Matt requested...



RBU 21-18F -- DRILLING PROCEDURE.pdf

John Egelston, PE Drilling Engineer XTO Energy Ofc: 505.333.3163

Fax: 505.333.3282 Mob: 505.330.6902

---- Forwarded by John Egelston/FAR/CTOC on 07/31/2008 09:24 AM -----



#### Matt\_Baker@blm.gov

07/31/2008 09:21 AM

To John\_Egelston@xtoenergy.com

cc Nancy\_Gibson@xtoenergy.com

Subject Re: RBU 21-18F

Verbal approval is granted.

CONDITIONS OF APPROVAL

- 1. A diverter shall be utilized while drilling the surface hole.
- 2. The production casing cement shall be a minimum of 200' above the surface casing shoe.
- 3. A hard copy of this request shall be sent to this office within 5 days from 7/29/08.

Matt Baker Senior Petroleum Engineer BLM Vernal Field Office Office # 435-781-4490 Cell # 435-828-4470 John\_Egelston@xto
energy.com

07/29/2008 08:03 AM "Matt Baker" <matt\_baker@blm.gov>

Nancy\_Gibson@xtoenergy.com

Subject

RBU 21-18F

Matt,

I was late in getting this drilling program change to regulatory. Would you mind looking it over and giving me a verbal while they are sending in the paperwork?

(See attached file: RBU 21-18F -- DRILLING PROCEDURE.pdf)

Thanks,

John Egelston, PE Drilling Engineer

XTO Energy

Ofc: 505.333.3163 Fax: 505.333.3282

Mob: 505.330.6902(See attached file: RBU 21-18F -- DRILLING PROCEDURE.pdf)

RBU 21-18F -- DRILLING PROCEDURE.pdf

#### XTO ENERGY INC.

**RBU 21-18F APD Data** July 31, 2008

Location: 2379' FNL & 834' FWL, Sec. 18, T10S, R20E County: Uintah

Bottomhole Location: 2450' FSL & 50' FWL, Sec. 18, T10S, R20E

State: Utah

GREATEST PROJECTED TD: 8770' MD/ 8650' TVD

APPROX GR ELEV: 5080'

OBJECTIVE: Wasatch/Mesaverde

Est KB ELEV: 5094' (14' AGL)

#### 1. **MUD PROGRAM:**

INTERVAL	0' to 2400'	2400' to 8770'
HOLE SIZE	12.25"	7.875"
MUD TYPE	FW/Spud Mud	KCl Based LSND / Gel Chemical
WEIGHT	8.4-8.80 ppg	8.6-9.2 ppg
VISCOSITY	NC	30-60 sec-qt <sup>-1</sup>
WATER LOSS	NC	8-15 cc's/30min

Remarks: Use fibrous materials as needed to control seepage and lost circulation. Pump high viscosity sweeps as needed for hole cleaning. Raise viscosity at TD for logging. Reduce viscosity after logging for cementing purposes. The mud system will be monitored visually/manually.

#### 2. **CASING PROGRAM:**

9.625" casing set at ±2400'MD/2466'TVD in a 12.25" hole filled with 8.8 ppg mud Surface Casing:

					Coll	Burst						
					Rating	Rating	Jt Str	ID	Drift	SF	SF	SF
Interval	Length	Wt	Gr	Cplg	(psi)	(psi)	(M-lbs)	(in)	(in)	Coll	Burst	Ten
0'-2400'	2400'	36#	J-55	ST&C	2020	3520	394	8.921	8.765	2.29	3.99	4.56

5.5" casing set at  $\pm 8770$ 'MD/8650'TVD in a 7.875" hole filled with 9.20 ppg mud. Production Casing:

					Coll	Burst						
					Rating	Rating	Jt Str	ID	Drift	SF	SF	SF
Interval	Length	Wt	Gr	Cplg	(psi)	(psi)	(M-lbs)	(in)	(in)	Coll	Burst	Ten
0'-8770'	8770'	17#	N-80	LT&C	6280	7740	348	4.892	4.767	1.92	2.36	2.33

Collapse and burst loads calculated at TVD with 0.1 psi/ft gas gradient back up.

#### 3. **WELLHEAD:**

- A. Casing Head: Larkin Fig 92 (or equivalent), 9" nominal, 2,000 psig WP (4,000 psig test) with 9-5/8" 8rnd thread on bottom (or slip-on, weld-on) and 11-3/4" 8rnd thread on top.
- B. Tubing Head: Larkin Fig 612 (or equivalent), 6.456" nominal, 5,000 psig WP, 5-1/2" 8rnd female thread on bottom (or slip-on, weld-on), 8-5/8" 8rnd thread on top.

#### **CEMENT PROGRAM:**

A. Surface:

9.625", 36#, J-55 (or equiv.), ST&C casing to be set at  $\pm 2400$ ' in 12.25" hole.

#### LEAD:

±243 sx of Premium Plus V Blend. (Type V/Poz/Gel) or equivalent, with dispersant, fluid loss, accelerator, & LCM mixed at 11.0 ppg, 3.82 ft<sup>3</sup>/sk, 22.95 gal wtr/sx.

TAIL:

350 sx Class G or equivalent cement with bonding additive, LCM, dispersant, & fluid loss mixed at 15.6 ppg, 1.2 cuft/sx

Total estimated slurry volume for the 9.625" surface casing is 1349.5 ft<sup>3</sup>. Slurry includes 75% excess of calculated open hole annular volume to 2400'.

B. Production: 5.5", 17#, N-80 (or equiv.), LT&C casing to be set at ±8770' in 7.875" hole.

#### LEAD:

±262 sx of Premium Plus V Blend. (Type V/Poz/Gel) or equivalent, with dispersant, fluid loss, accelerator, & LCM mixed at 11.6 ppg, 3.10 ft<sup>3</sup>/sk, 17.71 gal wtr/sx.

#### TAIL:

**400** sx Class G or equivalent cement with poz, bonding additive, LCM, dispersant, & fluid loss mixed at 13.0 ppg, 1.49 cuft/sx, 9.09 gal/sx.

Total estimated slurry volume for the 5.5" production casing is 1409.5 ft<sup>3</sup>. Slurry includes 15% excess of calculated open hole annular volume.

Note: The slurry design may change slightly based upon actual conditions. Final cement volumes will be determined from the caliper logs plus 15% or greater excess. The cement is designed to circulate on surface casing string. The production casing is designed for 1900' top of cement.

#### 5. LOGGING PROGRAM:

- A. Mud Logger: The mud logger will come on at intermediate casing point and will remain on the hole until TD. The mud will be logged in 10' intervals.
- B. Open Hole Logs as follows: Run Array Induction/SFL/GR/SP fr/TD (8770') to the bottom of the surface csg. Run Neutron/Lithodensity/Pe/GR/Cal from TD (8770') to 2400'. Run Gamma Ray to surface.

#### 6. FORMATION TOPS:

Please see attached directional plan.

#### 7. ANTICIPATED OIL, GAS, & WATER ZONES:

A.

Formation	Expected Fluids	TV Depth Top		
Wasatch Tongue	Oil/Gas/Water	4145		
Wasatch*	Gas/Water	4675		
Chapita Wells*	Gas/Water	5585		
Uteland Buttes	Gas/Water	6835		
Mesaverde*	Gas/Water	7725		

- B. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.
- C. There are no known potential sources of  $H_2S$ .
- D. The bottomhole pressure is anticipated to be between 4200 psi and 4600 psi.

#### 8. **BOP EQUIPMENT**:

Surface will utilize a diverter stack rated to no less than 500 psi.

Production hole will be drilled with a 3000 psi BOP stack.

Minimum specifications for pressure control equipment are as follows:

Ram Type: 11" Hydraulic double ram with annular, 3000 psi w.p.

Ram type preventers and associated equipment shall be tested to stack working pressure if isolated by test plug or to 70% of internal yield pressure of casing. Pressure shall be maintained for at least 10 minutes or until requirements of test are met, whichever is longer. If a test plug is utilized, no bleed-off pressure is acceptable. For a test not utilizing a test plug, if a decline in pressure of more than 10% in 30 minutes occurs, the test shall be considered to have failed. Valve on casing head below test plug shall be open during test of BOP stack.

Annular type preventers (if used) shall be tested to 50% of rated working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer.

As a minimum, the above test shall be performed:

- a. when initially installed:
- b. whenever any seal subject to test pressure is broken
- c. following related repairs: and
- d. at 30 day intervals

Valves shall be tested from working pressure side during BOPE tests with all down stream valves open.

When testing the kill line valve(s) shall be held open or the ball removed.

Annular preventers (if used) shall be functionally operated at least weekly.

Pipe and blind rams shall be activated each trip, however, this function need not be performed more than once a day.

A BOPE pit level drill shall be conducted weekly for each drilling crew.

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No.2 for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests. Pressure tests shall apply to all related well control equipment.

BOP systems shall be consistent with API RP53. Pressure tests will be conducted before drilling out from under casing strings which have been set and cemented in place. Test pressures for BOP equipment are as follows:

Annular BOP -- 1500 psi Ram type BOP -- 3000 psi Kill line valves -- 3000 psi Choke line valves and choke manifold valves -- 3000 psi Chokes -- 3000 psi Casing, casinghead & weld -- 1500 psi Upper kelly cock and safety valve -- 3000 psi Dart valve -- 3000 psi

Blowout preventer controls will be installed prior to drilling the surface casing plug and will remain in use until the well is completed or abandoned. Preventers will be inspected and operated at least daily to ensure good mechanical working order, and this inspection will be recorded on the daily drilling report. Preventers will be pressure tested before drilling casing cement plugs.

The BLM in Vernal, UT shall be notified, at least 24 hours prior to initiating the pressure test, in order to have a BLM representative on location during pressure testing.

- a. The size and rating of the BOP stack is shown on the attached diagram.
- b. A choke line and a kill line are to be properly installed.
- c. The accumulator system shall have a pressure capacity to provide for repeated operation of hydraulic preventers.
- d. Drill string safety valve(s), to fit all tools in the drill string, are to be maintained on the rig floor while drilling operations are in progress.
- e. See attached BOP & Choke manifold diagrams.

#### 9. **COMPANY PERSONNEL**:

<u>Name</u>	<u>Title</u>	Office Phone	<u>Home Phone</u>
John Egelston	Drilling Engineer	505-333-3163	505-330-6902
Bobby Jackson	Drilling Superintendent	505-333-3224	505-486-4706
Jeff Jackson	Project Geologist	817-885-2800	



0

550

#### Well Name: RBU 21-18F

San Juan Division Drilling Department

Calculation Method: Minimum Curvature

Geodetic Datum: North American Datum 1983

Lat: 39° 56' 48.070 N Long: 109° 43' 7.579 W



Azimuths to True North Magnetic North: 11.52°

> Magnetic Field Strength: 52582.6nT Dip Angle: 65.86° Date: 7/17/2008 Model: IGRF200510

#### SECTION DETAILS


Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	300.0	0.00	0.00	300.0	0.0	0.0	0.00	0.00	0.0	
3	815.2	15.46	302.50	809.0	37.1	-58.3	3.00	302.50	69.1	
4	3805.4	15.46	302.50	3691.0	465.3	-730.4	0.00	0.00	866.0	
5	4320.6	0.00	0.00	4200.0	502.4	-788.6	3.00	180.00	935.1	RBU 21-18F Requested BHL
6	8770.6	0.00	0.00	8650.0	502.4	-788.6	0.00	0.00	935.1	•


CASING DETAILS

TVD MD Name Size 2400.0 2465.9 9 5/8" 9-5/8 8650.0 8770.6 5 1/2" 5-1/2

#### FORMATION TOP DETAILS

TVDPath MDPath 4145.0 4265.6 Wasatch Tongue 4515.0 4635.6 Uteland Limestone 4675.0 4795.6 Wasatch 5585.0 5705.6 Chapita Wells 6835.0 6955.6 Uteland Buttes 7725.0 7845.6 Mesaverde





## **XTO Energy**

Natural Buttes Wells(NAD83) RBU 21-18F RBU 21-18F RBU 21-18F

Plan: Sundry'd Wellbore

### **Standard Planning Report**

17 July, 2008

#### XTO Energy, Inc.

#### Planning Report

Database:

EDM 2003.14 Single User Db

Company:

XTO Energy

Project:

Natural Buttes Wells(NAD83)

Site: Well: Wellbore:

Design:

RBU 21-18F RBU 21-18F RBU 21-18F

Local Co-ordinate Reference:

Well RBU 21-18F

TVD Reference:

MD Reference: North Reference: Rig KB @ 5094.0ft (Frontier #6) Rig KB @ 5094.0ft (Frontier #6)

Survey Calculation Method:

True

Minimum Curvature

Project

Natural Buttes Wells(NAD83), Vernal, UT

Map System: Geo Datum:

US State Plane 1983

North American Datum 1983

Sundry'd Wellbore

System Datum:

Mean Sea Level

Using Well Reference Point

Map Zone:

Utah Northern Zone

Site

From:

RBU 21-18F, T10S, R20E

Site Position:

Lat/Long

Northing: Easting:

3,145,078.81 ft

Latitude:

39° 56' 48.070 N

0.0 ft

2,139,910.26 ft

Longitude:

109° 43' 7.579 W

Position Uncertainty:

Slot Radius:

Grid Convergence:

1.17°

Well **Well Position** 

RBU 21-18F, S-Well to Wasatch/Mesaverde

+N/-S +E/-W

0.0 ft 0.0 ft Northing: Easting:

3,145,078.81 ft 2,139,910.26 ft Latitude: Longitude:

39° 56′ 48.070 N 109° 43' 7.579 W

**Position Uncertainty** 

0.0 ft

Wellhead Elevation:

5,080.0 ft

Ground Level:

5,080.0 ft

Wellbore

RBU 21-18F

Magnetics

**Model Name** 

Sundry'd Wellbore

Sample Date

Declination (°)

Dip Angle (°)

Field Strength

(nT)

IGRF200510

7/17/2008

11.52

65.86

52,583

Design

**Audit Notes:** 

Version:

Phase:

**PROTOTYPE** 

Tie On Depth:

0.0

**Vertical Section:** 

Depth From (TVD) (ft)

0.0

+N/-S (ft) 0.0

+E/-W (ft) 0.0

Direction (°)

302.50

Plan Sections										to a tark and the second of the second		
Measured			Vertical			Dogleg	Build	Turn				
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Rate	Rate	Rate	TFO			
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)	(°)	Target		
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00			
300.0	0.00	0.00	300.0	0.0	0.0	0.00	0.00	0.00	0.00			
815.2	15.46	302.50	809.0	37.1	-58.3	3.00	3.00	0.00	302.50			
3,805.4	15.46	302.50	3,691.0	465.3	-730.4	0.00	0.00	0.00	0.00			
4,320.6	0.00	0.00	4,200.0	502.4	-788.6	3.00	-3.00	0.00	180.00	RBU 21-18F Reque		
8,770.6	0.00	0.00	8,650.0	502.4	-788.6	0.00	0.00	0.00	0.00			

#### XTO Energy, Inc.

#### Planning Report

Database:

EDM 2003.14 Single User Db

Company: Project: Site:

XTO Energy

Natural Buttes Wells(NAD83) RBU 21-18F

Well: Wellbore: Design:

RBU 21-18F RBU 21-18F Sundry'd Wellbore Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method:

Well RBU 21-18F

Rig KB @ 5094.0ft (Frontier #6) Rig KB @ 5094.0ft (Frontier #6)

True

Minimum Curvature

anned Su	ui v <del>u</del> y				34 4242 95 2	in the second	1000			
	easured			Vertical			Vertical	Dogleg	Build	Turn
, ,	Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
	(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
	0.0	0.00	0.00	0.0	.0.0	0.0	0.0	0.00	0.00	0.00
	100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
	200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
	300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
	400.0	3.00	302.50	400.0	1.4	-2.2	2.6	3.00	3.00	0.00
	500.0	6.00	302.50	499.6	5.6	-8.8	10.5	3.00	3.00	0.00
	600.0	9.00	302.50	598.8	12.6	-19.8	23.5	3.00	3.00	0.00
	700.0	12.00	302.50	697.1	22.4	-35.2	41.7	3.00	3.00	0.00
	800.0	15.00	302.50	794.3	35.0	-54.9	65.1	3.00	3.00	0.00
	815.2	15.46	302.50	809.0	37.1	~58.3	69.1	3.00	3.00	0.00
	900.0	15.46	302.50	890.7	49.3	-77.3	91.7	0.00	0.00	0.00
	1,000.0	15.46	302.50	987.1	63.6	-99.8	118.3	0.00	0.00	0.00
	1,100.0	15.46	302.50	1,083.5	77.9	-122.3	145.0	0.00	0.00	0.00
	1,200.0	15.46	302.50	1,179.9	92.2	-122.3	171.6	0.00		
	1,200.0	15.46	302.50	1,179.9	106.5	-144.7 -167.2	198.3	0.00	0.00	0.00
									0.00	0.00
	1,400.0	15.46	302.50	1,372.6	120.9	-189.7	224.9	0.00	0.00	0.00
	1,500.0	15.46	302.50	1,469.0	135.2	-212.2	251.6	0.00	0.00	0.00
	1,600.0	15.46	302.50	1,565.4	149.5	-234.7	278.2	0.00	0.00	0.00
	1,700.0	15.46	302.50	1,661.8	163.8	-257.1	304.9	0.00	0.00	0.00
	1,800.0	15.46	302,50	1,758.2	178.1	-279.6	331.5	0.00	0.00	0.00
	1,900.0	15.46	302.50	1 051 5	192.5	202.1	250.2	0.00	0.00	0.00
				1,854.5		-302.1	358.2	0.00	0.00	0.00
	2,000.0 2,100.0	15.46	302.50	1,950.9	206.8	-324.6	384.8	0.00	0.00	0.00
		15.46	302.50	2,047.3	221.1	-347.1	411.5	0.00	0.00	0.00
	2,200.0	15.46	302.50	2,143.7	235.4	-369.5	438.1	0.00	0.00	0.00
	2,300.0	15.46	302.50	2,240.1	249.7	-392.0	464.8	0.00	0.00	0.00
	2,400.0	15.46	302.50	2,336.5	264.1	-414.5	491.5	0.00	0.00	0.00
	2,465.9	15.46	302.50	2,400.0	273.5	-429.3	509.0	0.00	0.00	0.00
9	5/8"									
	2,500.0	15.46	302.50	2,432.8	278.4	-437.0	518.1	0.00	0.00	0.00
	2,600.0	15.46	302.50	2,529.2	292.7	-459.4	544.8	0.00	0.00	0.00
	2,700.0	15.46	302.50	2,625.6	307.0	-481.9	571.4	0.00	0.00	0.00
	2,800.0	15.46	302.50	2,722.0	321.3	-504.4	598.1	0.00	0.00	0.00
	2,900.0	15.46	302.50	2,818.4	335.7	-526.9	624.7	0.00	0.00	0.00
	3,000.0	15.46	302.50	2,914.7	350.0	-549.4	651.4	0.00	0.00	0.00
	3,100.0	15.46	302.50	3,011.1	364.3	-571.8	678.0	0.00	0.00	0.00
	3,200.0	15.46	302.50	3,107.5	378.6	-594.3	704.7	0.00	0.00	0.00
	3,300.0	15.46	302.50	3,203.9	392.9	-616.8	731.3	0.00	0.00	0.00
	3,400.0	15.46	302.50	3,203.9	407.3	-639.3	751.3 758.0	0.00	0.00	0.00
	3,500.0	15.46		3,300.3 3,396.7						
	3,600.0		302.50		421.6	-661.7	784.6	0.00	0.00	0.00
	3,700.0	15,46	302.50 302.50	3,493.0	435.9	-684.2	811.3	0.00	0.00	0.00
	3,700.0	15,46	302.50	3,589.4	450.2	-706.7	837.9	0.00	0.00	0.00
	3,805.4	15.46	302.50	3,691.0	465.3	-730.4	866.0	0.00	0.00	0.00
	3,900.0	12.62	302.50	3,782.8	477.6	-749.7	889.0	3.00	-3.00	0.00
	4,000.0	9.62	302.50	3,880.9	488.0	-766.0	908.2	3.00	-3.00	0.00
	4,100.0	6,62	302.50	3,979.9	495.6	-777.9	922.4	3.00	-3.00	0.00
	4,200.0	3.62	302.50	4,079.5	500.4	-785.4	931.3	3.00	-3.00	0.00
	4 205 0									
	4,265.6	1.65	302.50	4,145.0	502.0	-788.0	934.3	3.00	-3.00	0.00
W	asatch Tor	•								
	4,300.0	0.62	302.50	4,179.4	502.4	-788.6	935.0	3.00	-3.00	0.00
	4,320.6	0.00	0.00	4,200.0	502.4	-788.6	935.1	3.00	-3.00	0.00
R	BU 21-18F	Requested BH	L							
	4,400.0	0.00	0.00	4,279.4	502.4	-788.6	935.1	0.00	0.00	0.00
	4,500.0	0.00	0.00	4,379.4	502.4	-788.6	935.1	0.00	0.00	0.00

#### XTO Energy, Inc.

#### Planning Report

Database: Company: EDM 2003.14 Single User Db

XTO Energy

Project:

Natural Buttes Wells(NAD83)

Site: Well: RBU 21-18F

Wellbore: Design: RBU 21-18F RBU 21-18F Sundry'd Wellbore Local Co-ordinate Reference:

TVD Reference:

North Reference:

Survey Calculation Method:

Well RBU 21-18F

Rig KB @ 5094.0ft (Frontier #6) Rig KB @ 5094.0ft (Frontier #6)

True

Minimum Curvature

Measured		and the second of the second	Vertical	Sample of the Control		Vertical	Dogleg	Build	Turn
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
(ft)	(°)	(°)	(ft)	+N/-5 (ft)	+E/-VV (ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
							•••••		
4,600.0 4,635.6	0.00	0.00	4,479.4 4,515.0	502.4 502.4	-788.6	935.1	0.00	0.00	0.00
	0.00	0.00	4,515.0	502.4	-788.6	935.1	0.00	0.00	0.00
Uteland Lir									
4,700.0	0.00	0.00	4,579.4	502.4	-788.6	935.1	0.00	0.00	0.00
4,795.6	0.00	0.00	4,675.0	502.4	<b>-</b> 788.6	935.1	0.00	0.00	0.00
Wasatch									
4,800.0	0.00	0.00	4,679.4	502.4	-788.6	935.1	0.00	0.00	0.00
4,900.0	0.00	0.00	4,779.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,000.0	0.00	0.00	4,879.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,100.0	0.00	0.00	4,979.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,200.0	0.00	0.00	5,079.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,300.0	0.00	0.00	5,179.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,400.0	0.00	0.00	5,279.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,500.0	0.00	0.00	5,379.4	502.4 502.4	-788.6	935.1	0.00	0.00	0.00
5,600.0	0.00	0.00	5,479.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,700.0	0.00	0.00	5,579.4	502.4	-788.6	935.1	0.00	0.00	0.00
5,705.6	0.00	0.00	5,585.0	502.4	-788.6	935.1	0.00	0.00	0.00
Chapita We			0,000.0						•
•		0.00	F 070 4	500.4	700.0	005.4	0.00	0.00	0.00
5,800.0 5,900.0	0.00 0.00	0.00 0.00	5,679.4 5,779.4	502.4 502.4	-788.6 -788.6	935.1 935.1	0.00 0.00	0.00 0.00	0.00
- •			•		-788.6		0.00	0.00	0.00
6,000.0	0.00	0.00	5,879.4 5,979.4	502.4	-766.6 -788.6	935.1	0.00	0.00	0.00
6,100.0 6,200.0	0.00 0.00	0.00 0.00	5,979.4 6,079.4	502.4 502.4	-788.6	935.1 935.1	0.00	0.00	0.00
			•						
6,300.0	0.00	0.00	6,179.4	502.4	-788.6	935.1	0.00	0.00	0.00
6,400.0	0.00	0.00	6,279.4	502.4	-788.6	935.1	0.00	0.00	0.00
6,500.0	0.00	0.00	6,379.4	502.4	-788.6	935.1	0.00	0.00	0.00
6,600.0	0.00	0.00	6,479.4	502.4	-788.6	935.1	0.00	0.00	0.00
6,700.0	0.00	0.00	6,579.4	502.4	-788.6	935.1	0.00	0.00	0.00
6,800.0	0.00	0.00	6,679.4	502.4	-788.6	935.1	0.00	0.00	0.00
6,900.0	0.00	0.00	6,779.4	502.4	-788.6	935.1	0.00	0.00	0.00
6,955.6	0.00	0.00	6,835.0	502.4	-788.6	935.1	0.00	0.00	0.00
Uteland Bu	ttes								
7,000.0	0.00	0.00	6,879.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,100.0	0.00	0.00	6,979.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,200.0	0.00	0.00	7,079.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,300.0	0.00	0.00	7,179.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,400.0	0.00	0.00	7,279.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,500.0	0.00	0.00	7,379.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,600.0	0.00	0.00	7,479.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,700.0	0.00	0.00	7,579.4	502.4	-788.6	935.1	0.00	0.00	0.00
7,700.0	0.00	0.00	7,579.4 7,679.4	502.4 502.4	-700.0 -788.6	935.1	0.00	0.00	0.00
7,800.0	0.00	0.00	7,679.4	502.4 502.4	-788.6	935.1	0.00	0.00	0.00
		0.00	1,125.0	302.4	-700,0	900, I	0.00	0.00	0.00
Mesaverde	0.00	0.00	7 770 4	E00.4	-788.6	935.1	0.00	0.00	0.00
7,900.0 8,000.0		0.00	7,779.4 7,879.4	502.4	-788.6	935.1	0.00	0.00	0.00
,	0.00	0.00		502.4					
8,100.0	0.00	0.00	7,979.4	502.4	-788.6	935.1	0.00	0.00	0.00
8,200.0	0.00	0.00	8,079.4	502.4	-788.6	935.1	0.00	0.00	0.00
8,300.0	0.00	0.00	8,179.4	502.4	-788.6	935.1	0.00	0.00	0.00
8,400.0	0.00	0.00	8,279.4	502.4	-788.6	935.1	0.00	0.00	0.00
8,500.0	0.00	0.00	8,379.4	502.4	-788.6	935.1	0.00	0.00	0.00
8,600.0	0.00	0.00	8,479.4	502.4	-788.6	935.1	0.00	0.00	0.00
8,700.0	0.00	0.00	8,579.4	502.4	-788.6	935.1	0.00	0.00	0.00
8,770.6	0.00	0.00	8,650.0	502.4	-788.6	935.1	0.00	0.00	0.00

#### XTO Energy, Inc.

#### Planning Report

Database:

EDM 2003.14 Single User Db

Company:

XTO Energy

Project:

Natural Buttes Wells(NAD83)

Site: Well:

RBU 21-18F RBU 21-18F

Wellbore: Design:

RBU 21-18F Sundry'd Wellbore Local Co-ordinate Reference:

TVD Reference:

Well RBU 21-18F

MD Reference:

North Reference: Survey Calculation Method: Rig KB @ 5094.0ft (Frontier #6)

Rig KB @ 5094.0ft (Frontier #6)

True

Minimum Curvature

Planned Survey				To Service a personal control of the	
Measured			Vertical	Vertical	 uild Turn
Depth (ft)	Inclination (°)	Azimuth (°)	Depth +N/-S (ft) (ft)	+E/-W Section (ft)	ate Rate 00ft) (°/100ft)
5 1/2"					

Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
RBU 21-18F Requeste - plan hits target - Circle (radius 30.0)		0.00	4,200.0	502.4	-788.6	3,145,564.96	2,139,111.48	39° 56' 53.034 N	109° 43' 17.703 W

Casing Points					•			
	Measured Depth	Vertical Depth				Casing Diameter	Hole	
	(ft)	(ft)		Name		(")	(")	
	2,465.9	2,400.0	9 5/8"			9-5/8	12-1/4	
	8,770.6	8,650.0	5 1/2"			5-1/2	7-7/8	

Formations		and the second second second second	Park of Agriculture, Something to the Asset Asset Sold
Measured Depth (ft)	Vertical Depth (ft)	Name	Dip Dip Direction Lithology (°) (°)
4,265.6	4,145.0	Wasatch Tongue	0.00
4,635.6	4,515.0	Uteland Limestone	0.00
4,795.6	4,675.0	Wasatch	0.00
5,705.6	5,585.0	Chapita Wells	0.00
6,955.6	6,835.0	Uteland Buttes	0.00
7,845.6	7,725.0	Mesaverde	0.00

FORM 9

### STATE OF UTAH MENT OF NATURAL RESOURCES.

DEPARTMENT OF NATURAL RESOL DIVISION OF OIL, GAS AND M		5. LEASE DESIGNATION AND SERIAL NUMBER: U-013769-A
SUNDRY NOTICES AND REPORT	S ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below or drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL	7. UNIT OF CA AGREEMENT NAME: RIVERBEND UNIT	
1. TYPE OF WELL OIL WELL GAS WELL OTHER		8. WELL NAME and NUMBER: RBU 21-18F
2. NAME OF OPERATOR:  XTO ENERGY INC.	PHONE NUMBER:	9. API NUMBER: 4304738554  10. FIELD AND POOL, OR WILDCAT:
3. ADDRESS OF OPERATOR:  382 CR 3100  CITY AZTEC  STATE NM ZI  4. LOCATION OF WELL		NATURAL BUTTES
FOOTAGES AT SURFACE: 2379' FSL & 834' FWL		COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 10S	20E S	STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
NOTICE OF INTENT (Submit in Duplicate)  ACIDIZE  ALTER CASING	DEEPEN FRACTURE TREAT	REPERFORATE CURRENT FORMATION SIDETRACK TO REPAIR WELL
Approximate date work will start:  CASING REPAIR  CHANGE TO PREVIOUS PLANS	NEW CONSTRUCTION OPERATOR CHANGE	TEMPORARILY ABANDON TUBING REPAIR
CHANGE TUBING  SUBSEQUENT REPORT (Submit Original Form Only)  CHANGE WELL NAME	PLUG BACK	VENT OR FLARE WATER DISPOSAL
Date of work completion:  CHANGE WELL STATUS  COMMINGLE PRODUCING FORMATIONS	PRODUCTION (START/RESUME)  RECLAMATION OF WELL SITE	WATER SHUT-OFF  ✓ OTHER: AUGUST '08
8/31/2008 CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION	MONTHLY REPORT
Attached is XTO Energy's monthly report for the period of	· · · · · · · · · · · · · · · · · · ·	es, etc.
NAME (PLEASE PRINT) WANETT MCCAULEY SIGNATURE WANETT MCCAULEY  MANUAL MA	FILE CLERK  Output  DATE  9/3/2008	
This space for State use only)	J DI	ECENTER .

RECEIVED
SEP 0 8 2008

8/1/2008 - 8/31/2008 Report run on 9/2/2008 at 2:43 PM

Riverbend Uni	it 21-18F - Natural Buttes, 18, 10S, 20E, Uintah, Utah, ,
·	AFE: 717118 Objective: Drill & Complete a Natural Buttes gas well
8/12/2008	RIG 70% RIGGED DOWN 20 % RIGGED UP, MATTEN BOARDS AND SUB SPOTTED IN
==	======================================
8/13/2008	RIG 100% MOVED OVER AND 90% RIGGED UP
==	======================================
8/14/2008	FINISH RIG UP , CIRC THRU GAS BUSTER CHECK FOR LEAKS, DO A PRE SPUD INSPECTION , STRAP BHA , PICK UP DIRC TOOLS SPUD @ 22:00 ON 8-13-08
	Riverbend Unit 21-18F
8/15/2008	DRILL/F 328' TO 1090', HAD TO REPAIR FLAIR IGNITER, D/F 1090' TO 1496'
==	======================================
8/16/2008	DRILL/F 1496' TO 2364', CIRC SWEEP OUT BUILD & PUMP PILL, PULL OUT OF HOLE TO RUN CSG ,L/D 8" DIRC TOOLS AND DC'S, HOLD S/M WITH CASERS RUN CASING
==	======================================
8/17/2008	RUN 53 JTS 9 5/8 36# J-55 CSG WITH FLOAT EQUIPMENT SET @ 2,322' KB.  CMT WITH 280 SKS 11#, 3.82 YIELD, 23 GAL/SK WATER LEAD CMT FALLOW WITH  225 SKS 15.8#, 1.15 YIELD, 5 GAL/SK WATER TAIL CMT. IN TWO HRS CMT FELL 13'  FILL BACK SIDE WITH 19 SKS OF READY MIX ,GOOD RETURNS FLOATS HELD 35 BLS CMT  TO RESERVE PIT, NIPPLE UP BOP START TEST BLEW OUT O-RING  ON DRLG FLANGE PICK UP BOP REPLACE 0-RINGS TEST BOP BLEW OUT O-RINGS AGAIN  BREAK OFF BOTTOM FLANGE WT ON WHI
8/18/2008	CHANGE OUT BOTTOM FLANGE ON BOP, TEST PIPE RAMS , CHOKE AND BLINDS TO 5000 AND LOW 250, ANNULAR TO 1500, STRAP AND PICK UP BHA, TRIP IN HOLE, DRILL OUT CMT & FLOAT EQUIPMENT/D/F 2365' TO 3025
==	Riverbend Unit 21-18F
8/19/2008	Directional Drilling f/3025' to 4500' KB. Drilled 1475' for 23.50 hrs @ 62.77 ft/hr. Last Deviation Survey @ 4443', 1.25 Degrees, 184.79 Azi. Drilling w/KCL Water 8.4# 27 Vis.
5=	======================================
8/20/2008	Drilling f/4500' to 5900' KB. Drilled 1400' for 23.50 hrs @ 59.57 ft/hr. Last Deviation Survey @ 5836' 2.06 Degrees, 144.67 Azi. Drilling w/KCL Water 8.6# 27 Vis.  Drilling f/4500' to 5900' KB. Drilled 1400' for 23.50 hrs @ 59.57 ft/hr. Last Deviation Survey @ 5836' 2.06 Degrees, 144.67 Azi. Drilling w/KCL Water 8.6# 27 Vis.

8/1/2008 - 8/31/2008 Report run on 9/2/2008 at 2:43 PM

	======================================
8/21/2008	Drilling f/5900' to 6990' KB. Drilled 1090' for 23.50 hrs @ 46.38 ft/hr. Last Deviation Survey @ 6551' 1.69 Degrees, 169.42 Azi. Drilling w/KCL Water 8.5# 26 Vis 2.7% KCL.
	======================================
8/22/2008	Drilling f/6990' to 7775' KB. Drilled 785' for 23.50 hrs @ 33.40 ft/hr. Last Deviation Survey @ 7546' 2.31 Degrees, 184.79 Azi. Mud Up @ 7418' KB w/Sweeps. 8.6# 33 Vis.
	======================================
8/23/2008	Drilling f/7775' to 8400' KB. Drilled 625' for 23.50 hrs @ 26.60 ft/hr. Last Deviation Survey @ 7886' 1.63 Degrees, 172.04 Azi. Sea Mud/Pac 8.9# 32 Vis. #1 Mud Pump Down from 7:00 pm till 1:00 am 6 hrs Fuel Pump Problems.
	======================================
8/24/2008	Drld f/8400' to 8413' KB. Drld 13' for 1 hr @ 13.00 ft/hr (Rig Hrs). (Pason Bit Hrs .6 hrs for 13' @ 21.66 ft/hr). TOOH For Bit Trip. LD Directional Tools. PU New Bit & MM. TIH To 8413'. Drld f/8413' to 8692'KB. Drld 279' for 11.5 hrs @ 24.26 ft/hr (Rig Hrs). (Pason Bit Hrs. Drld 279' for 9.3 hrs @ 30.0 ft/hr). Last Deviation Survey @ 8356' 1.69 Degrees, 163.28 Azi. Sea Mud/Pac 9.1# 37 Vis.
	======================================
8/25/2008	Drld f/8692' to 9002' KB. Drld 310' for 12 hrs @ 25.83 ft/hr (Rig Hrs). (Pason Bit Hrs Drld 310' for 10.7 hrs @ 28.97 ft/hr). Drillers TD @ 9002' KB 08/24/08 @ 06:00 pm. TOOH For Open Hole Logs. Run Open Hole Logs w/Baker. Loggers TD 9007' KB. Last Deviation Survey @ 8928' 1.25 Degrees. Sea Mud/Pac 9.2# 38 Vis. Called Carol w/State Of Utah & Jamie w/BLM on 8/24/08 @ 6:15 pm to run 5.500" Csg & Cmt on 8/25/08 around 9:00 pm.
	======================================
8/26/2008	RD Open Hole Loggers. LD Mud Motor. TIH to 2200'. Slip & Cut Drill Line. TIH to 9007' (Loggers TD). No Fill. Circulate. TOOH LD Pipe & BHA. Pull Wear Bushing. RU & Start Running 5.500" Casing.
	======================================
8/27/2008	Finish Running 5.500" 17# Seah 80 LT&C Casing to 8990.00' KB. Float Collar @ 8941.83' KB. Circulate. RU & Cement 5.500" Production Casing w/Halliburton. Lead Cement 11.0#, 3.1 Yield, 18.12 Gal/sk, 205 Sacks (113.2 bbls). Tail Cement 13.4#, 1.49 Yield, 7.14 Gal/sk, 665 Sacks (176.5 bbls). Displaced w/207.5 bbls of 2% KCL Treated Water. Floats Held. RD Rig. Rig Released @ 6:00 pm 8/26/08.

FORM 9 STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING U-013769-A 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS N/A 7. UNIT or CA AGREEMENT NAME: Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. RIVERBEND UNIT 1 TYPE OF WELL 8. WELL NAME and NUMBER: GAS WELL 🔽 OIL WELL OTHER **RBU 21-18F** 2. NAME OF OPERATOR: 9. API NUMBER: XTO ENERGY INC. 4304738554 10. FIELD AND POOL, OR WILDCAT: 3. ADDRESS OF OPERATOR: PHONE NUMBER: CITY AZTEC ZIP 87410 STATE NM NATURAL BUTTES 382 CR 3100 (505) 333-3100 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2379' FSL & 834' FWL COUNTY: UINTAH QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 10S 20E S STATE: UTAH CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA 11. TYPE OF ACTION TYPE OF SUBMISSION REPERFORATE CURRENT FORMATION ACIDIZE DEEPEN NOTICE OF INTENT (Submit in Duplicate) ALTER CASING FRACTURE TREAT SIDETRACK TO REPAIR WELL TEMPORARILY ABANDON Approximate date work will start: NEW CONSTRUCTION CASING REPAIR OPERATOR CHANGE TUBING REPAIR CHANGE TO PREVIOUS PLANS CHANGE TUBING PLUG AND ABANDON VENT OR FLARE WATER DISPOSAL SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK (Submit Original Form Only) WATER SHUT-OFF CHANGE WELL STATUS PRODUCTION (START/RESUME) Date of work completion: COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE OTHER: SEPTEMBER '08 9/30/2008 MONTHLY REPORT RECOMPLETE - DIFFERENT FORMATION CONVERT WELL TYPE DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Attached is XTO Energy's monthly report for the period of 9/01/2008 thru 9/30/2008.

NAME (PLEASE PRINT), WANETT MCCAULEY

SIGNATURE WANTET MCCAULEY

DATE FILE CLERK

10/3/2008

(This space for State use only)

RECEIVED

OCT 0 6 2008

9/1/2008 - 9/30/2008 Report run on 10/1/2008 at 1:30 PM

Riverbend Unit 21-18F - Natural Buttes, 18, 10S, 20E, Uintah, Utah, Roosevelt,

AFE: 717118

Objective: Drill & Complete a Natural Buttes gas well

9/2/2008

MIRU CHS WL. RIH W/4.65" OD GR TO 8933'. POH W/ TLS, RIH w/ GR/CCL/CBL logging tls. Tgd @ 8933'. Run CBL under 750 psig fr 8933'-2700' FS. Log indic TOC @ 2900'. POH & LD logging tls. RU pmp trk. PT csg to 2500 psig for 30" & 5000 psig for 10" TST (OK). POH & RDMO WL. Rpts suspd until further activity.

\_\_\_\_\_\_ Riverbend Unit 21-18F ------

9/5/2008

MIRU Perf O Log. RIH w/3-1/8" csg guns loaded w/Titan EXP-3323-361T, 22.7 gm chrgs. Perf stage 1 MV intv fr/8483-86', 812-14', 8565-68', 8646-49', & 8825-28' w/2 SPF (120 deg phasing, 0.36'' EHD, 35.63" pene., 33 holes). POH& LD perf guns. SWI & RDMO WLU. STAGE WORK

9/8/2008

Rig up Frac Tech & Perf O Log. Hold saftey meeting w/ all party's. BD MV stg #1 perfs w/2% KCL wtr & EIR. A. perfs fr/8483-8828' w/1250 gals of 7-1/2% NEFE HCl ac & 50 Bio-BS @ 10 bpm dwn 5-1/2" csg. BD perfs @ 3515 psig. Ppd 259 bls ttl. BO @ 5500 psig. Surge balls off perfs & SD 20". Fracd MV stg #1 perfs fr/8483-8828', dwn 5-1/2" csg w/ 27,804 gals wtr,60Q N2 foam gelled fld (Turquoise 20# Foam Frac), 2% KCl wtr carrying 80,189 #SLC 20/40 sd. Max sd conc 3 ppg. ISIP 4245 psig, 5" SIP 3863 psig. .93G. Used 986 mscf of N2, 922 BLW (stq 1).

RIH & set 6K CBP @ 8455'. PT plg to 6,000 psig, gd tst. RIH w/3-1/8" csg guns loaded w/Titan EXP-3323-361T, 22.75 gm chrgs. Perf stage 2 MV intv fr/8330-36', 8340-46, & 8424-26'w/2 SPF (120 deg phasing, 0.36" EHD, 35.63" pene., 31 holes). BD MV stg #2 perfs w/2% KCL wtr & EIR. A. perfs fr/8330-8426' Spear head w/1250 gals of 7-1/2% NEFE HCl ac BD perfs @ 4984 psig. Fracd MV stg 2 perfs fr/8330-8426', dwn 5-1/2" csg w/ 22,176 gals wtr, 60Q N2 foam gelled fld (Turquoise 20# Foam Frac), 2% KCl wtr carrying 62,093 #SLC 20/40 sd. Max sd conc 3 ppg. Screened out w/ 154 of 193 bls flush. Est 4,900 #'s snd in WB. Used 785 mscf of N2, 528 BLW (stg 2). RIH w/3-1/8" csg guns loaded w/Titan EXP-3323-361T, 22.75 gm chrgs. Tg snd @ 7700'. ( 300' of fill). POH w/ WL. OWU on 24/64 ck 5200 psig.

STAGE WORK

9/1/2008 - 9/30/2008 Report run on 10/1/2008 at 1:30 PM

9/9/2008

SICP 0 psig. RUFrac Tech & Perf O Log WL. Hold saftey meeting w/all party's. RIH w/3-1/8" csg quns loaded w/Titan EXP-3323-361T, 22.75 qm chrqs. Perf stage 3 MV intv fr/7531' - 34', 7718' - 20', 7805' - 08' & 7921' - 25' w/2 SPF (120 deg phasing, 0.36" EHD, 35.63" pene., 28 holes). BD MV stg # 3 perfs w/2% KCL wtr & EIR. A. perfs fr/7531' - 7925' w/1250 gals of 7-1/2% NEFE HCl ac & 42 Bìo-BS @ 10 bpm dwn 5-1/2" csg. BD perfs @ 5980 psig. Ppd 192 bls ttl. Balled off perfs @ 5500 psig. Surge balls off perfs & SD 20". Fracd MV stg #3 perfs fr/7531' - 7925', dwn 5-1/2" csg w/21,882 gals wtr,700 N2 foam gelled fld (Turquoise 20# Foam Frac), 2% KCl wtr carrying 49,850 lbs 30/50 White & 18,645 lbs SLC 20/40 sd. Max sd conc 4 ppg. ISIP 3316 psig, 5" SIP 3076 psig. 0.83G. Used 893 mscf of N2, 713 BLW (stg 3). RIH & set 6K CBP @ 6750'. PT plg to 6,000 psig, gd tst. RIH w/3-1/8" csg guns loaded w/Titan EXP-3323-361T, 22.75 gm chrgs. Perf stage 4 CW intv fr/6340' - 43', 6672' - 78' & 6724' - 31' w/2 SPF (120 deg phasing, 0.36" EHD, 35.63" pene., 35 holes). BD CW stg #4 perfs w/2% KCL wtr & EIR. A. perfs fr/6340' - 6343' w/1250 gals of 7-1/2% NEFE HCl ac & 53 Bio-BS @ 10 bpm dwn 5-1/2" csg. BD perfs @ 2600 psig. Ppd 180 bls ttl. Balled off @ 3200 psig. Surge balls off perfs & SD 20". Fracd CW stg 4 perfs fr/6340' - 6731', dwn 5-1/2" csg w/20,748 gals wtr, 700 N2 foam gelled fld (Turquoise 20# Foam Frac), 2% KCl wtr carrying 61,500 lbs 30/50 White & 21,768 lbs SLC 20/40 sd. Max sd conc 4 ppg. ISIP 2351 psig, 5" SIP 2300 psig. .80G. Used 971 mscf of N2, 675 BLW (stg 4). RIH & set 6K CBP @ 5010'.PT plg to 6,000 psig, gd tst. RIH w/3-1/8" csg guns loaded w/Titan EXP-3323-361T, 22.75 gm chrgs. Perf stage 5 WA intv fr/4963' - 66' & 4973' - 76'w/2 SPF (120 deg phasing, 0.36" EHD, 35.63" pene., 19 holes). BD WA stg #5 perfs w/2% KCL wtr & EIR. A. perfs fr/4963'-4976' w/1250 gals of 7-1/2% NEFE HCl ac, BD perfs @ 3000 psig. Fracd WA stg 5 perfs fr/4963' - 4976', dwn 5-1/2" csg w/12,180 gals wtr, 70Q N2 foam gelled fld (Turquoise 20# Foam Frac), 2% KCl wtr carrying 19,576 lbs 30/50 White & 10,924 lbs SLC 20/40 sd. Max sd conc 4 ppg. ISIP 2718 psig, 5" SIP 2650 psig. 0.99 FG. Used 365 mscf of N2, 292 BLW (stg 5). RIH w/ WL set CBP @ 4800' FS. SWI & RDMO frac equip & WLU. 3128 BLWTR. Rpts suspended until further acitivity.

9/15/2008

SICP 700 psig. MIRU Temples WS #2. Unable to BD csg. MIRU CHS WLU, RIH set CBP @ 4,750'. POH RDMO WLU. BD csg, ND frac vlv, NU BOP. PU & TIH w/4-3/4" Hurricane mill, safety sub, BRS, 2 3/8" SN & 144 jts 2-3/8", L-80, 4.7#, EUE 8rd tbg. EOT @ 4,650'. RU pwr swivel. SWI & SDFN. 3,128 BLWTR ttl.

9/16/2008

SITP 0 psig, SICP 0 psig. Cont to TIH w/4-3/4" Hurricane mill, SS, BRS, SN, & 2-3/8" tbg. DO 5-1/2" CBP's @ 4,750', 4,800', 5,010' (CO 15' sd abv plg), & 6,750' (CO 20' sd abv plg). TIH tgd sd @ 7,844'. CO 142' sd to 7,986'. Unable to unload cuttings & sd, well died. POH w/ tbg abv perfs to 4,891. Wait overnight on AFU. SWI & SDFN. 3,128 BLWTR ttl.

9/17/2008

SITP 0 psig, SICP 450 psig Opn well on a 30/64 ck. Cont to TIH w/4-3/4" Hurricane mill, SS, BRS, SN, & 2-3/8" tbg. Tgd fill @ 7,831'. MIRU AFU, estb circ and CO 624' of sd to CBP @ 8,455'. FCP 500 psig. TIH & CO 142' of sd to PBTD @ 8,942'. Circ well cln & LD 14 jts of tbg. Ld 257 jts 2-3/8", 4.7#, L-80, 8rd tbg on hgr w/EOT @ 8,502' & SN @ 8,500'. RU swb tls. RIH w/ XTO's 1.90" tbg broach to SN @ 8,500' (no ti spts). POH & LD broach. ND BOP. NU WH. Ppd off bit & 1/2 of BRS @ 1,800 psig. SWIFPBU & SDFN. RDMO AFU & Temples WS #2 and equip. Ttl fl ppd 800 bbls, Ttl fl rec 1,200 bbls, 2,728 BLWTR ttl.

9/1/2008 - 9/30/2008 Report run on 10/1/2008 at 1:30 PM

	======================================
9/18/2008	SITP 700 psig. SICP 1950 psig. 7:00 OWU. F.0 BO, 172 BLW, 32 & 12/64 ck, 10 hrs, Rets of gas, wtr & tr of sd. FTP 1200 psig. SICP 2000 psig. 2556 BLWTR.
	======================================
9/19/2008	FTP 1300 psig. SICP 1700 psig. F.O BO, 186 BLW, 18 hrs, 12 & 18/64 ck. Rets of gas, wtr & tr of sd. 2370 BLWTR. Well shut in 6 for rig ops on RBU 12-18F.
	======================================
9/20/2008	FTP 750 psig. SICP 1200 psig. F.O BO, 160 BLW, 24 hrs, 18/64 ck. Rets of gas, wtr & tr of sd. 2210 BLWTR.
	======================================
9/21/2008	FTP 775 psig. SICP 1000 psig. F.0 BO, 117 BLW, 24 hrs, $18/64$ ck. Rets of gas, wtr & tr of sd. 2103 BLWTR.
	======================================
9/22/2008	FTP 800 psig. SICP 1000 psig. F.O BO, 90 BLW, 22 hrs, 18/64 ck. Rets of gas, wtr & tr of sd. 2013 BLWTR. SWI 2 hrs for rig ops on RBU 12-18F.
	======================================
9/23/2008	FTP 600 psig. SICP 850 psig. F.O BO, 91 BLW, 24 hrs, 18/64 ck. Rets of gas & wtr. 1922 BLWTR. Gas tstd 7% N2. SWI & WO prod equip.

### -

#### STATE OF UTAH

	DEPARTMENT OF NATURAL			T CIXIII S
ι	DIVISION OF OIL, GAS			5. LEASE DESIGNATION AND SERIAL NUMBER: U-013769-A
SUNDRY	NOTICES AND RE	PORTS ON WEL	LS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
Do not use this form for proposals to drill no drill horizontal la	ew wells, significantly deepen existing we terals. Use APPLICATION FOR PERMI	ells below current bottom-hole dep T TO DRILL form for such proposa	th, reenter plugged wells, or to	7. UNIT OF CA AGREEMENT NAME: RIVERBEND UNIT
1. TYPE OF WELL OIL WELL		8. WELL NAME and NUMBER: RBU 21-18F		
2. NAME OF OPERATOR: XTO ENERGY INC.				9. API NUMBER: 4304738554
3. ADDRESS OF OPERATOR: 382 CR 3100	AZTEC	NM <sub>ZIP</sub> 87410	PHONE NUMBER: (505) 333-3100	10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL  FOOTAGES AT SURFACE: 2379'    QTR/QTR, SECTION, TOWNSHIP, RANGE	-SL & 834' FWL	10S 20E S		COUNTY: UINTAH STATE:
OLIFOK APPE	PODDIATE DOVES TO L	NOIGATE MATURE	OF NOTICE DEPO	UTAH
TYPE OF SUBMISSION	ROPRIATE BOXES TO I		YPE OF ACTION	RT, OR OTHER DATA
NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start:  SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion:  10/31/2008  12. DESCRIBE PROPOSED OR CO		DEEPEN  PRACTURE  NEW CONS S OPERATOR  PLUG AND  PLUG BACI  PRODUCTI  RMATIONS RECLAMAT  RECOMPLE  Ty show all pertinent details in	ETREAT STRUCTION R CHANGE ABANDON K ON (START/RESUME) FION OF WELL SITE ETE - DIFFERENT FORMATION Icluding dates, depths, volume	REPERFORATE CURRENT FORMATION  SIDETRACK TO REPAIR WELL  TEMPORARILY ABANDON  TUBING REPAIR  VENT OR FLARE  WATER DISPOSAL  WATER SHUT-OFF  OTHER: OCTOBER 08  MONTHLY REPORT
				RECEIVED  NOV 1 0 2008  DIV. OF OIL, GAS & MINING
	R M. HEMBRY		FILE CLERK	
NAME (PLEASE PRINT) SENTIN E		embry DA	11/5/2008	
(This space for State use only)		-		

(See Instructions on Reverse Side)

10/1/2008 - 10/31/2008 Report run on 11/4/2008 at 12:50 PM

Riverbend Unit 21-18F - Natural Buttes, 18, 10S, 20E, Uintah, Utah, , Roosevelt, Flowing

AFE: 717118

Objective: Drill & Complete a Natural Buttes gas well

10/7/2008

MI 84' of 8" .188W steel bare gas line to loc. Std pre-fabrication of 3" mtr tie into 4" .188W steel bare sales line. Compl pre-fabrication of 4" gas ancor. Compl 6-2", 3-3"& 3-4" welds. Compl x-ray of 4-2", 3-3" & 2-4" welds. SDFN.

10/8/2008

Compl pre-fabrication & inst of 1-4" vlv onto main 8" .188W steel bare gas line. Compl inst of 2-2" blow down assemblies. Compl tie of 3" mtr run to 4" .188W FB welded sales line. Compl inst of 4" gas ancor. Compl 8-4", 6-2" welds. Compl x-raying 20-4", 3-2" & 1-3" welds. SDWO PT sched for week of

10/13/08.

10/9/2008

Compl pre-fabrication & inst of 1-4" vlv onto main 8" .188W steel bare gas line. Compl inst of 2-2" blow down assemblies. Compl tie of 3" mtr run to

4" .188W FB welded sales line. Compl inst of 4" gas ancor. Compl 8-4", 6-2" welds. Compl x-raying 20-4", 3-2" & 1-3" welds. Pipeline inst compl.

Project Complete.

10/24/2008

The River Bend Unit 21-18F was first delivered to Questar through the Hill Creek Check @ 11:45a.m., Today 10-24-08. IFR 1200 MCFPD.

This well is in Uintah, County.

This well is on Roosevelt Lease Operator route #206.

This is a WA/MV well.

Accounting # 165660.

AFE # 717118.

XTO allocation meter # RS 1518 RF.

RTU # 0997.

Hill Creek Check CDP # 287510.

Tank # F 1222.

Form 3160-5 (August 2007)

#### UNITED STATES DEPARTMENT OF THE INTERIOR

## BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires July 31, 2010

5. Lease Serial No.

VOCIMEIS	NOTICES	AND	REPORTS	ON	WELLS
4 MILLING Y	NULLIGA	MINU		~,,	

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals. U-013769-A 6. If Indian, Allottee or Tribe Name

doubled them the	, ,			]N/A	and the second s		
SUBMIT IN TRIPLICAT		7. If Unit or CA/Agreement, Name and/or No. RIVERBEND UNIT					
1. Type of Well Oil Well X Gas Well Other  2. Name of Operator				8. Well Name a RBU 21-18F			
XTO Energy Inc.  3a. Address		3b. Phone No. (include ar	eu code) 33-3100	43-047-385			
BIII. 2373 FBE & 001 FME	Description) EC 18-T10S-R20E EC 18-T10S-R20E			NATURAL BUTTES WASATCH-MESAVERDE  11. County or Parish, State UINTAH UT			
12. CHECK APPROPRIATE	E BOX(ES) TO INI	DICATE NATURE OF I	NOTICE, REP	ORT, OR OTHI	ER DATA		
TYPE OF SUBMISSION		TY	PE OF ACTION	1			
Notice of Intent  Subsequent Report  Final Abandonment Notice	Acidize  Alter Casing  Casing Repair  Change Plans  Convert to Inject		Reclama Recomp Tempors Water D	lete arily Abandon visposal	Water Shut-Off Well Integrity  X Other 1ST DELIVERY		
13. Describe Proposed or Completed Operation (clear)	ly state all pertinent deta	ails, including estimated start	ing date of any p	proposed work and	d approximate duration thereof		

Describe Proposed of Completed Operation Recently state an portion of the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

XTO Energy, Inc. first delivered this well to Questar Gas Management @ 11:45 a.m., Friday, 10/24/2008.

IFR 1,200 MCFPD.

Mtr #RS 1518 RF

**RECEIVED** DEC 0 5 2008

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed) BARBARA NICOL	Title FILE CLERK	
Signature Barbara Nicol	Date 10/27/2008	
THIS SPACE FOR F	EDERAL OR STATE OFFICE US	E
Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	certify that Office	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL, GAS AND MINING	5. LEASE DESIGNATION AND SERIAL NUMBER: U-013769-A
SUNDRY NOTICES AND REPORTS ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	7. UNIT OF CA AGREEMENT NAME: RIVERBEND UNIT
1. TYPE OF WELL OIL WELL GAS WELL OTHER	8. WELL NAME and NUMBER: RBU 21-18F
2. NAME OF OPERATOR:	9. API NUMBER: 4304738554
XTO ENERGY INC.  3. ADDRESS OF OPERATOR: PHONE NUMBER:	10. FIELD AND POOL, OR WILDCAT:
382 CR 3100 CITY AZTEC STATE NM ZIP 87410 (505) 333-3100	NATURAL BUTTES
FOOTAGES AT SURFACE: 2379' FSL & 834' FWL	COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 10S 20E S	STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
TYPE OF SUBMISSION TYPE OF ACTION	REPERFORATE CURRENT FORMATION
NOTICE OF INTENT (Submit in Duplicate)  ACIDIZE  DEEPEN  FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will start: CASING REPAIR NEW CONSTRUCTION	TEMPORARILY ABANDON
CHANGE TO PREVIOUS PLANS OPERATOR CHANGE	TUBING REPAIR
CHANGE TUBING PLUG AND ABANDON	VENT OR FLARE
SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK	WATER DISPOSAL
(Submit Original Form Only)  Date of work completion:  CHANGE WELL STATUS  PRODUCTION (START/RESUME)	WATER SHUT-OFF
COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE	OTHER: DECEMBER 08  MONTHLY REPORT
CONVERT WELL TIFE	
DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volue XTO Energy Inc. has nothing to report for the period of 11/01/2008 thru 11/30/2008.	
NAME (PLEASE PRINT) JENNIFER M. HEMBRY	CLERK
SIGNATURE SONNIGER M. Hembry DATE 11/5/2008	
(This space for State use only)	RECEIVE

DEC 0 9 2008

#### FORM 9

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES	
DIVISION OF OIL, GAS AND MINING	5. LEASE DESIGNATION AND SERAL NUMBER: U-013769-A
SUNDRY NOTICES AND REPORTS ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	7. UNIT OF CA AGREEMENT NAME: RIVERBEND UNIT
1. TYPE OF WELL OIL WELL GAS WELL OTHER	8. WELL NAME and NUMBER: RBU 21-18F
2. NAME OF OPERATOR: XTO ENERGY INC.	9. API NUMBER: 4304738554
3. ADDRESS OF OPERATOR: 382 CR 3100 STATE NM ZIP 87410 PHONE NUMBER: (505) 333-3100	10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL	
FOOTAGES AT SURFACE: 2379' FSL & 834' FWL	COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 10S 20E S	STATE: <b>UTAH</b>
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
TYPE OF SUBMISSION TYPE OF ACTION	
ACIDIZE DEEPEN	REPERFORATE CURRENT FORMATION
NOTICE OF INTENT (Submit in Duplicate)  ALTER CASING  FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will start: CASING REPAIR NEW CONSTRUCTION	TEMPORARILY ABANDON
CHANGE TO PREVIOUS PLANS OPERATOR CHANGE	TUBING REPAIR
CHANGE TUBING PLUG AND ABANDON	VENT OR FLARE
SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK	WATER DISPOSAL
(Submit Original Form Only)	WATER SHUT-OFF
Date of work completion:  CHANGE WELL STATUS  PRODUCTION (START/RESUME)	브
12/31/2008 COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE	OTHER: DECEMBER 08  MONTHLY REPORT
CONVERT WELL TYPE RECOMPLETE - DIFFERENT FORMATION	MONTHET REPORT
DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volume XTO Energy Inc. has nothing to report for the period of 12/01/2008 thru 12/31/2008.	
MAME (DI EASE DOINT) JENNIFER M. HEMBRY	CLERK
NAME (FLENSPRINT)	
SIGNATURE Almury M. Hemby DATE 1/5/2009	
This space for State use only)	

Form 3160-5 (August, 1999)

#### **UNITED STATES** DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT**

#### FORM APPROVED OMB No. 1004-0135

Expires: November 30, 2000

5. Lease Serial No.

U-013769A

#### SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an

6	If Indian, Allottee or Tribe Name
	N/A

abandoned well. Use	N/A	N/A			
SUBMIT IN TRIPLIC	CATE - Other Instructio	ns on reverse side	7. If Unit or CA/Agreement, Name and/or No.		
1. Type of Well	891016035-A				
Oil Well X Gas Well	8. Well Name and No.	8. Well Name and No.			
2. Name of Operator			River Bend Unit 21-18F		
XTO Energy, Inc.	9. API Well No.				
3a. Address		3b. Phone No. (include area code)			
978 North Crescent Road, Roose	velt, UT. 84066	435-722-4521	10. Field and Pool, or Exploratory Area		
4. Location of Well (Footage, Sec., T., R., M., 654' FNL & 619' FEL NE/NE Sec. 18, 10S. 106. 106. 106. 107. 108. 108. 108. 108. 108. 108. 108. 108	Natural Buttes 11. County or Parish, State Uintah County, Utah	11. County or Parish, State			
12. CHECK APPROPRIATE	BOX(ES) TO INDICAT	TE NATURE OF NOTICE, R	REPORT OR OTHER DATA		
TYPE OF SUBMISSION		TYPE OF ACTIO	N		
Notice of Intent  Subsequent Report  Final Abandonment Notice	Acidize Altering Casing Casing Repair Change Plans Convert to Injection	Fracture Treat X Reclama New Construction Recomp	olete Other arily Abandon Interm Reclaimation	·····	

Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval. a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Reserve pit reclaimed & reseeded on12/15/2008

RECEIVED MAR 0 5 2009

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct Name (Printed Typed)				
Heather Butterfield	Title	Regulatory Complia	nce Techi	nician
Signature Heather Butterly 18		3/05/2009		
THIS SPACE FOR EDERAL OR STA	re offici	E USE	1. 1.4	
Approved by	Title		:	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office			

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



## UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED OMB NO. 1004-0137 Expires July 31, 2010

	WE	LL CO	MPLETION	OR RE	COMPL	ETION F	REPOR	T AND I	LOG			5. Lease S		
la Tyr	e of Well								<del></del>			<u>U-013</u>	769A	
1u. 13p	o or wen		Well 🗶 Ga	•	Dry	Othe	er				1	6. If Indiar	ı, Allotee	or Tribe Name
b. Т <b>у</b> р	e of Completic	n:	X New We	" 🗌 W	ork Over	Deep	en [	Plug B	ack 🗍	Diff.Re	svr,.	N/A	<u> </u>	
			Other							_	1		_	ement Name and No.
2. Name	of Operator										=-	8. Lease N	BEND I	
3. Addre	nergy Inc.	·									- 1		21-18I	
		_					3a.	Phone N	o. (include	e area c	ode)	9. API We	21-101 Il No.	<u> </u>
	R 3100 I ion of Well (Re	Aztec,	NM 87410	nd in agas	udan oo	I. F. J. I		50!	<u>5-333-3</u>	100		43-04	7-385	54
At sur	c						-	•			Ī	0. Field and	Pool, o	r Exploratory
	2379	' FSL	& 834' FW	L	per	Hsn	1116	NIE	N/FC	) a	ļ.	NATUR	AL BU	TTES WASATCH-MV
At ton	prod. interval	renorted b	salou.				* P	ECF	10-		11	Survey of	R., M., o or Area	or Block and
	prod. Intorvar	eported t	CIOW	•			k.	1	מונ ב	9	_			3-T10S-R20E
At tota	l depth 24	70 i 100	L & 10 <b>1</b> )	UTATT			#7 *	FEB '	IVEC 8 200			2. County of	or Parish	13. State
14. Date			Date T.D. Rea			16 1	Doto Com		GAS & 1	MMM)	3   U	INTAH		UT
	- j	1.5.	Suit 1.D. Rea	cricu		110. 1	Date Con	UP OF OIL	GAS G	v to Pre	id II	7. Elevation	ons (DF,	RKB, RT, GL)*
7/2	5/08		3/26/08				או <b>ס</b> " [_ מעום	26/08	X Road	, 10 1 10	····	E0001	<b>AT</b>	
	Depth: MD			9. Plug B	ack T.D.:	MD		42'	1 20	Denth I	Bridge Plu	5080'	MD	
	TVD		3882	J		TVD		522	20.	Doptii	Jinge I it	_	TVD	
21. Type	Electric & Oth	er Mecha	nical Logs Ru	n (Submit	copy of ea	ch)		<u></u>	22. V	Vas well	cored?	X No		Yes (Submit analysis)
									i	Vas DST		X No		Yes (Submit report
GR/CCI	CBL D	cor	np2.	CN						Direction	al Survey?	No No	==	Yes (Submit copy)
23. Casing	g and Liner Re	cord (Rep	oort all strings	set in wel	1)				<del></del>				LEAU	
Hole Size	Size/Grade	Wt.(#f	t.) Top (M	D) Bott	om (MD)	Stage Ce			Sks. &		ry Vol.	Cement	Ton*	A Pull d
20"	14"/J55	106.	5# SURI	, ,	10'	Dep	otn		f Cement	(E	BL)			Amount Pulled
2-1/4"	9.6/J55	36#			323'				EDIMIX			0		ļ ————
7-7/8"	5.5/S80	17#			90'			505	G			0		
/	3.3/200	<del> / 11</del>	BURE		,30.			870 P	REMIUM			290	0'	
		<del> </del> -				<del></del>								
		<del> </del>												
24. Tubing	Record	<u> </u>												
Size	-T	مغم ا												
2-3/8"	Depth Set		Packer Depth (	MD)	Size	Depth Se	et (MD)	Packer	Depth (MD)	1 3	Size	Depth Se	t (MD)	Packer Depth (MD)
	ing Intervals		<del></del>			26 P 6		<del></del>		1				
	Formation		Ton			26. Perfo			<del></del>				·	
4)	WASATCH-I		Top		ottom		erforated			Size	N	o. Holes		Perf. Status
3)	MADAICH-I	MA.	4963	- 88	328'	49	63' -	88281		).36"		141		OPEN
C)	······································		<del>                                     </del>					<del></del>					ļ	<u></u>
D)	<del></del>	<del></del>	<del> </del>				···						1	
<del></del>			<u> </u>											
	racture, Treati	nent, Cer	nent Squeeze,	Etc.					· · · · · · · · · · · · · · · · · · ·					
	Depth Interval	<del></del>	<del> </del>			· · · · · · · · · · · · · · · · · · ·			d Type of N					
496	3' - 8828	' 	A. w/	6250 ga	ls of '	7-1/2%	NEFE F	ICl aci	d. Fra	c'd v	v/104,7	790 gal:	s wtr,	60-70Q N2
			foam	gelled	fld (T	ırquise	20# E	oam Fr	ac), 2%	KCl	wtr ca	arrying	130,9	26# 30/50
	<del></del>		White	& 193 <i>,</i>	619# SI	C 20/4	0 sd.		-					
	<del></del>											····		
3. Producti	on - Interval A													
Date First Produced	Test Date	Hours Tested	Test	Oil	Gas	Water	Oil Grav Corr. Al	rity ot	Gas	P	roduction l	Method		
0/24/08	10/26/08	24	Production	BBL 2	MCF 1080	BBL <b>93</b>	Con. Al	n .	Gravity				ET OUT	TNICT
Choke Size	Tbg. Press.	Csg.	24	Oil	Gas	Water	Gas: O	il	Well Statu	s			FLOWI	LVJ
20/64"	Flwg. SI 570	Press. 750	Hr	BBL 2	MCF 1080	BBL	Ratio							
	ion-Interval B		<del></del>	<u>. 4</u>	1 1000	93	1		P	RODUC	:ING			
Date First	Test	Hours	Test	Oil	Gas	Water	Oil Grav	ity	Gas	F	odu-ti .	4-41-1		
roduced	Date	Tested	Production	BBL	MCF	BBL	Corr. AP		Gas Gravity	1 1	oduction N	vietnod		
Choke	Tbg. Press.	Csg.	24	Oil	Gas	Water	Gas: Oi	<del></del>	Well Statu		<del></del>			
ize	Flwg. SI	Press.	Hr.	BBL	MCF	BBL	Ratio	"	wen statu	3				
	~.					1	1							

<u>i</u>												
28b. Product	tion - Inter	val C					<b></b>	· •				
Date First Produced	Test Date	Ho Tes		st oduction	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method		
Choke Size	Tbg. Pre Flwg. SI	ess. Csg Pre	s. 24 ss. Hr.		Oil BBL	Gas MCF	Water BBL	Gas: Oil Ratio	Well Status	•		
28c. Produc	tion-Inter	val D	1		l	<u></u>		<u> </u>				
Date First Produced	Test Date	Hot Tes		st oduction	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method		
Choke Size	Tbg. Pre Flwg. SI	ss. Csg Pre:			Oil BBL	Gas MCF	Water BBL	Gas: Oil Ratio	Well Status	Vell Status		
29. Disposit		(Sold, used	for fuel, v		;.)	I	TO BE	SOLD				
30. Summa	ry of Porc	us Zones	(Include A	(quifers):			<del></del>	<del></del>	31 Formati	on (Log) Markers		
Show all	l important g depth inte	zones of porval tested,	rosity and	contents the	ereof: Cor of open, flo	ed intervals wing and sl	and all dril hut-in press	l-stem tests, ures and	31. Politian	on (Log) markers		
Format	tion	Т				Б.					Тор	
rormat	Formation Top Bottom		ottom	Descriptions, Contents, etc.					Name	Meas.Depth		
								GREEN RI	VER	1283		
	-				1.				MAHOGENY	BENCH	2150	
									WASATCH	TONGUE	4314	
										LIMESTONE	4662	
	[								WASATCH			
											4827	
					1			•	CHAPITA		5663	
	}		}						UTELAND 1		7014	
			-						MESAVERD	Ε	7844	
	Ī											
	.					•						
	}											
		•										
			1				-					
					1					· · · · · · · · · · · · · · · · · · ·		
2. Addition	nal remark:	s (include	plugging p	procedure	):							
3. Indicate	which iten	ne hava ha	e attached	l by place	a a chacl	in the en	neoneiste l	Owner.				
		nical Logs			ig a CHECK	_						
		or plugging			ation		gic Report Analysis	DST Rep	Directio	nal Survey		
I hereby	certify tha	t the fores	oing and	attached i	nformatio	n is comp	lete and or	orrect as determine	ned from all available	e records (see attached in	nstructions)*	
			. 5			. эр			an arando		ion detions)	
Name (ple	ease print)	LORR	ID.B	INGHAM	)			Т	itle <u>SR. REGU</u>	LATORY COMPLIANC	IE TECH	
Signature		S	wat	1/1	200	lan	2	· 	Date <u>2/13/09</u>			
		/ )										
						<del></del>						
e 18 U.S.C es any false	C. Section e, fictitious	1001 and s or fraudi	Title 43 lalent state	U.S.C. Se	ection 121	2, make i	it a crime o anv matt	for any person ker within its inris	nowingly and willfu	illy to make to any depa	artment or agency of the Unite	

Continued on page 3)

Brent Martin/FAR/CTOC

02/12/2009 06:09 PM

To Lorri Bingham/FAR/CTOC@CTOC

cc Justin Niederhofer

bcc

Subject Fw: RBU #21-18F

RECEIVED FEB 18 2009

Lorri:

The BHL for the above well is:

2470' FNL and 101' FWL @ 9002' MD/8881' TVD in Section 18, T10S, R-20E.

I am going to leave the Weatherford Directional Survey and Survey Plat along with my calculations on your chair.

Brent H Martin XTO Farmington Drilling Manager O (505) 333-3110 C (505) 320-4074 brent\_martin@xtoenergy.com

----- Forwarded by Brent Martin/FAR/CTOC on 02/12/2009 06:06 PM -----



Lorri Bingham/FAR/CTOC 02/07/2009 09:24 AM

To Brent Martin/FAR/CTOC@CTOC, Justin Niederhofer/FAR/CTOC@CTOC

CC

Subject RBU #21-18F

Good morning, gentlemen!

Could you please forward a directional survey & BHL for this well?

Thanks,

Lorri Bingham Regulatory Compliance Technician XTO Energy, Inc./Farmington (505) 333-3204


# Using Wentherford Survey @ 6551' MD/6431 TUD and extangulating coordinates down to 9002' MD/8881'TVD total depth

Wentherford worth displacement = 471.77ff

Distance from N. Line of Sec 18, TIUS, A 20E = 5321' - 2379' - 471.77' = 2470' FALL

Wenthenford west displacement = 733.77'
Distance from W. Line of Sec 18, TIOS, RZOE =
834' - 733.77 = 100.73' OR 101'FWL

BHL = 2470' FNL and 101' FWL of Sec 18, TIUS, RZOE at total depth of 9002' MD/8881' TVD



Using Weatherford Survey @ 6551' MD/6431 TVD and extrapolating coordinates down to 9002' MD/8881'TVD total depth

Wentherford worth displacement = 471.77ff

Distance from N. Line of Sec 18, TIUS, AZUE = 5321' - 2379' - 471,77' = 2470' FAIL

Wenthenford west displacement = 733.77'
Distance from W. Line of Sec 18, T105, R20E =
834' - 733.77 = 100.73' OR 101' FWL


BHL = 2470' FNL and 101' FWL of Sec 18, TIUS, A 20E at total depth of 9002' MD/8881'TVD



Project: UINTAH COUNTY, UT Site: RBU 21-18F PAD Well: RBU 21-18F

Well: KBU 21-167
Wellbore: Wellbore #1
Design: Wellbore #1
Latitude: 39° 56' 48.070 N
Longitude: 109° 43' 7.573 W
Ground Level: 5080.00 WELL @ 5094.00ft (Original Well Elev)








Project: UINTAH COUNTY, UT Site: RBU 21-18F PAD Well: RBU 21-18F Wellbore: Wellbore #1

Design: Wellbore #1 Latitude: 39° 56' 48.070 N Longitude: 109° 43' 7.573 W Ground Level: 5080.00 WELL @ 5094.00ft (Original Well Elev)







Client Well

: XTO Energy : RBU 21-18F

**Location**: Uintah County

License

**UWI #:** 

Page: 1

Date: 8/20/2008

File: 4014444

ense	:				UVVI #:							
	Vertical Section Calculated Along Azimuth 302.48°											
	KB Elevation = 5094.00ft GR. Elevation = 5080.00ft											
	MD	Inc	Azi	TVD	North	East	V'Sect	D'Leg	Build	Turn		
	ft	deg	deg	ft	ft	ft	ft	°/100	°/100	°/100		
0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
1	85.00	0.00	176.04	85.00	0.00	0.00	0.00	0.00	0.00	207.11		
2	181.00	2.69	319.54	180.96	1.71	-1.46	2.15	2.80	2.80	149.48		
2 3	273.00	4.81	331.17	272.76	6.74	-4.72	7.60	2.44	2.30	12.64		
4	365.00	5.94	318.54	364.36	13.68	-9.7 <b>4</b>	15.56	1.77	1.23	-13.73		
7	000.00	0.01	010.01	00 1.00	.0.00	• • • • • • • • • • • • • • • • • • • •						
5	457.00	7.50	314.67	455.73	21.47	-17.16	26.01	1.76	1.70	-4.21		
6	548.00	9.44	306.92	545.73	30.13	-27.35	39.25	2.47	2.13	-8.52		
7	639.00	11.88	302.29	635.16	39.62	-41.24	56.06	2.84	2.68	-5.09		
8	732.00	14.88	300.42	725.62	50.78	-59.63	77.57	3.26	3.23	-2.01		
9	824.00	15.88	299.67	814.33	62.99	-80.75	101.95	1.11	1.09	-0.82		
10	915.00	16.63	297.92	901.69	75.25	-103.08	127.37	0.98	0.82	-1.92		
11	1009.00	17.19	296.29	991.63	87.71	-127.42	154.58	0.78	0.60	-1.73		
12	1102.00	16.69	300.92	1080.59	100.66	-151.20	181.60	1.55	-0.54	4.98		
13	1195.00	16.56	299.92	1169.71	114.13	-174.14	208.19	0.34	-0.14	-1.08		
14	1286.00	16.88	300.92	1256.86	127.39	-196.71	234.35	0.47	0.35	1.10		
15	1379.00	18.00	301.79	1345.58	141.89	-220.51	262.22	1.24	1.20	0.94		
16	1472.00	17.94	302.04	1434.05	157.06	-244.87	290.91	0.11	-0.06	0.27		
17	1563.00	17.31	302.79	1520.77	171.83	-268.13	318.46	0.74	-0.69	0.82		
18	1655.00	17.19	302.67	1608.64	186.58	-291.08	345.74	0.14	-0.13	-0.13		
19	1747.00	17.57	301.92	1696.44	201.26	-314.31	373.22	0.48	0.41	-0.82		
20	1041 00	17.25	300.92	1786.13	215.92	-338.31	401.34	0.47	-0.34	-1.06		
20	1841.00 1935.00	16.13	300.92	1876.17	229.70	-361.52	428.32	1.20	-1.19	-0.53		
21 22	2028.00	15.44	299.04	1965.66	242.25	-383.49	453.59	0.84	-0.74	-1. <u>4</u> 8		
23	2123.00	15.31	298.29	2057.26	254.33	<b>-405.59</b>	478.72	0.25	-0.14	-0.79		
24	2217.00	14.81	295.54	2148.03	265.39	<b>-427.36</b>	503.03	0.93	-0.53	-2.93		
27	2217.00	17.01	200.01	21 10.00	200.00	,_,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	000.00	0.00	-			
25	2309.00	14.74	294.10	2236.99	275.24	-448.65	526.28	0.41	-0.08	-1.57		
26	2397.00	14.38	291.54	2322.17	283.82	-469.03	548.08	0.84	-0.41	-2.91		
27	2489.00	14.88	296.92	2411.19	293.37	<del>-4</del> 90.19	571.06	1.57	0.54	5.85		
28	2582.00	15.00	303.29	2501.05	305.38	-510.90	594.98	1.77	0.13	6.85		
29	2673.00	14.00	308.92	2589.15	318.76	-529.31	617.69	1.90	-1.10	6.19		
30	2766.00	14.00	310.54	2679.39	333.14	-546.61	640.01	0.42	0.00	1.74		
31	2861.00	15.00	313.42	2771.37	349.06	-564.28	663.46	1.30	1.05	3.03		
32	2954.00	15.75	312.67	2861.04	365.89	-582.30	687.70	0.83	0.81	-0.81		
33	3048.00	15.06	310.04	2951.66	382.39	-601.03	712.36	1.04	-0.73	-2.80		
34	3142.00	13.31	308.92	3042.79	397.04	-618.80	735.22	1.88	-1.86	-1.19		
			- · - ·			00 / 0=	<b>755 55</b>	404	0.00	2.00		
35	3234.00	12.50	312.54		410.43	-634.37	755.55	1.24		3.93		
36	3328.00	12.19	313.42	3224.29	424.13	-649.08	775.31	0.39	-0.33	0.94		
					_							



Client

: XTO Energy : RBU 21-18F

Well

Location : Uintah County

License :

**UWI #:** 

Page: 2

Date: 8/20/2008 File: 4014444

Vertical Section Calculated Along Azimuth 302.48°

	Vertical Section Calculated Along Azimuth 302.48°											
		KB Elev	vation = 5	5094.00ft	GR. Ele	vation = 5						
	MD	Inc	Azi	TVD	North	East	V'Sect	D'Leg	Build	Turn		
	ft	deg	deg	ft	ft	ft	ft	°/100	°/100	°/100		
37	3420.00	12.94	312.17	3314.09	437.72	-663.77	795.00	0.87	0.82	-1.36		
38	3515.00	13.88	311.92	3406.50	452.47	<b>-</b> 680.13	816.72	0.99	0.99	-0.26		
39	3609.00	13.44	309.17	3497.84	466.91	-696.99	838.70	0.83	-0.47	-2.93		
40	3702.00	12.63	312.92	3588.45	480.66	-712.81	859.43	1.26	-0.87	4.03		
41	3795.00	11.06	309.64	3679.46	493.27	-727.13	878.28	1.84	-1.69	-3.53		
42	3887.00	9.31	308.54	3770.01	503.54	-739.75	894.44	1.91	-1.90	-1.20		
43	3981.00	7.75	305.00	3862.97	511.91	-750.89	908.33	1.75	-1.66	-3.77		
44	4072.00	6.06	309.79	3953.31	518.51	-759.60	919.23	1.96	-1.86	5.26		
45	4165.00	2.50	305.17	4046.03	522.82	-765.04	926.12	3.84	-3.83	-4.97		
46	4258.00	0.88	257.92	4138.99	523.84	-767.39	928.66	2.16	-1.74	-50.81		
47	4350.00	1.19	210.29	4230.98	522.87	-768.57	929.13	0.96	0.34	-51.77		
48	4443.00	1.25	184.79	4323.96	521.02	-769.14	928.62	0.58	0.06	-27.42		
49	4686.00	1.69	178.67	4566.88	514.80	-769.28	925.39	0.19	0.18	-2.52		
										40.40		
50	4778.00	1.50	161.67	4658.84	512.30	-768.87	923.70	0.55	-0.21	-18.48		
51	4871.00	1.44	121.17	4751.81	510.54	-767.48	921.59	1.10	-0.06	-43.55		
52	5337.00	1.63	127.42	5217.65	503.48	-757.21	909.14	0.05	0.04	1.34		
53	5836.00	2.06	144.67	5716.39	491.85	-746.39	893.76	0.14	0.09	3.46		
54	5962.00	1.69	137.04	5842.32	488.64	-743.81	889.87	0.35	-0.29	-6.06		
		0.40	45405	0007.04	47475	704 70	074.00	0.40	0.40	2 56		
55	6457.00	2.19	154.67		474.75	-734.79	874.80	0.16	0.10	3.56		
56	6551.00	1.69	169.42	6430.99	471.77	-733.77	872.33	0.75	-0.53	15.69		

Bottom Hole Closure 872.34ft Along Azimuth 302.74°

Sundry Number: 23816 API Well Number: 43047385540000

STATE OF UTAH			FORM 9	
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		5.LEASE DESIGNATION AND SERIAL NUMBER: U013769-A		
SUNDF	RY NOTICES AND REPORTS	S ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
	oposals to drill new wells, significantl reenter plugged wells, or to drill horiz n for such proposals.		7.UNIT or CA AGREEMENT NAME: RIVER BEND	
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: RBU 21-18F	
2. NAME OF OPERATOR: XTO ENERGY INC			9. API NUMBER: 43047385540000	
3. ADDRESS OF OPERATOR: PHONE NUMBER: 382 Road 3100 , Aztec, NM, 87410 505 333-3145 Ext			9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2379 FSL 0834 FWL			COUNTY: UINTAH	
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSW Section: 18 Township: 10.0S Range: 20.0E Meridian: S			STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA				
TYPE OF SUBMISSION	TYPE OF ACTION			
	✓ ACIDIZE	ALTER CASING	CASING REPAIR	
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME	
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE	
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION	
2/9/2012	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK	
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION	
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON	
DRILLING REPORT	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL	
	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION	
Report Date:				
	WILDCAT WELL DETERMINATION	OTHER	OTHER:	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  XTO Energy Inc. performed an acid treatment on this well per the following:1/27/2012: MIRU SLU. SN @ 8,499'. RU & RIH w/fishing tls, fish plngr & BHBS fr SN. POH & LD fihing tls. RDMO SLU. 2/6/2012: MIRU acid pumper. Pmp 250 gal 15% HCl ac w/adds dwn tbg & flsh w/ 34 bbls 2% KCl wtr. ND Pmp 500 gal 15% HCl ac w/adds dwn csg & flsh w/36 bbls 2% KCl wtr. RDMO acid pumper. 2/8/2012: Swab. BFL @ 6,500' FS. S 0 BO, 26 BW. 9 runs, 9 hrs. FFL @ 6,900' FS. 2/9/2012: Cont swab. BFL @ 6,800' FS. S 0 BO, 5 BW. 4 runs, 4 hrs. KO well flwg.  FFL @ 6,400' FS. RWTP.				
NAME (PLEASE PRINT) Barbara Nicol	<b>PHONE NUN</b> 505 333-3642	IBER TITLE Regulatory Compliance Ted		
SIGNATURE N/A		DATE 3/9/2012	DATE 3/9/2012	

Sundry Number: 75528 API Well Number: 43047385540000

	FORM 9			
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING			5.LEASE DESIGNATION AND SERIAL NUMBER: U013769-A	
SUNDRY NOTICES AND REPORTS ON WELLS			6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.			7.UNIT or CA AGREEMENT NAME: RIVER BEND	
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: RBU 21-18F	
2. NAME OF OPERATOR: XTO ENERGY INC			9. API NUMBER: 43047385540000	
<b>3. ADDRESS OF OPERATOR:</b> PO Box 6501, Englewood, CO, 80155  9HONE NUMBER: 303 397-3727 Ext			9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2379 FSL 0834 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSW Section: 18 Township: 10.0S Range: 20.0E Meridian: S			COUNTY: UINTAH	
			STATE: UTAH	
11. CHECI	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA	
TYPE OF SUBMISSION				
	✓ ACIDIZE	ALTER CASING	CASING REPAIR	
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME	
Approximate date work will start:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE	
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION	
9/9/2016	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK	
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION	
SPUD REPORT Date of Spud:				
☐ DRILLING REPORT	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON	
	L TUBING REPAIR	☐ VENT OR FLARE	☐ WATER DISPOSAL ☐	
Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION	
	WILDCAT WELL DETERMINATION	OTHER	OTHER:	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  XTO Energy Inc. performed an Acid Treatment on this well per the following: 09/06/16: MIRU SLU. Rec PCS dual pad plngr. Tgd @ 8,916' (26' Fill). SWI for acid job. RDMO SLU. 09/08/16: MIRU pump truck.  Pumpd 500 gals 15% HCL w/add & 25 bbls flush down csg, pumpd 250 gals 15% HCL w/add & 33 bbls flush down tbg. RDMO pump truck.  09/09/16: MIRU SWU. Cycld plngr to surf & RWTP 9/9/16. RDMO SWU.  NAME (PLEASE PRINT)  PHONE NUMBER TITLE				
NAME (PLEASE PRINT) Rhonda Smith	<b>PHONE NUME</b> 505 333-3215	BER TITLE Regulatory Clerk		
SIGNATURE N/A		<b>DATE</b> 10/21/2016		